



US010729457B2

(12) **United States Patent**  
**Lenker et al.**

(10) **Patent No.:** **US 10,729,457 B2**  
(45) **Date of Patent:** **\*Aug. 4, 2020**

(54) **STEERABLE ENDOLUMINAL PUNCH WITH CUTTING STYLET**

(2013.01); *A61B 2017/00327* (2013.01); *A61B 2017/00862* (2013.01); *A61B 2018/00351* (2013.01); *A61B 2018/00577* (2013.01);  
(Continued)

(71) Applicant: **Indian Wells Medical, Inc.**, Laguna Beach, CA (US)

(58) **Field of Classification Search**

CPC . A61B 17/34; A61B 17/3403; A61B 17/3417; A61B 17/3421; A61B 17/3478; A61B 2017/00247; A61B 2017/00309; A61B 2017/00323; A61M 25/0105; A61M 25/0133; A61M 25/0138; A61M 25/0147; A61M 25/06; A61M 25/065

(72) Inventors: **Jay A. Lenker**, Laguna Beach, CA (US); **James A. Carroll**, Long Beach, CA (US); **Eugene M. Breznock**, Winters, CA (US)

See application file for complete search history.

(\* ) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 300 days.

This patent is subject to a terminal disclaimer.

(56) **References Cited**

U.S. PATENT DOCUMENTS

5,725,512 A 3/1998 Swartz et al.  
6,471,697 B1 10/2002 Lesh  
(Continued)

(21) Appl. No.: **15/904,230**

(22) Filed: **Feb. 23, 2018**

(65) **Prior Publication Data**

US 2018/0289388 A1 Oct. 11, 2018

**Related U.S. Application Data**

(63) Continuation-in-part of application No. 15/441,025, filed on Feb. 23, 2017, now Pat. No. 10,485,579.  
(Continued)

OTHER PUBLICATIONS

International Search Report and Written Opinion from IA No. PCT/US2018/000274 dated Dec. 13, 2018.

*Primary Examiner* — Ryan J. Severson

(74) *Attorney, Agent, or Firm* — Crockett & Crockett, PC; K. David Crockett, Esq.

(51) **Int. Cl.**

*A61B 17/34* (2006.01)  
*A61B 17/32* (2006.01)

(Continued)


(57) **ABSTRACT**

A transseptal needle or punch is described wherein the distal end of the transseptal needle is able to articulate laterally out of the longitudinal axis of the steerable transseptal needle. The transseptal needle includes a blunted distal end configuration that is minimally traumatic. Under control by the user or a computer, the transseptal needle can be articulated to generate various curves with high bending force. The transseptal needle is configured for use with an introducer which can also include side windows.

(52) **U.S. Cl.**

CPC .. *A61B 17/320016* (2013.01); *A61B 17/3478* (2013.01); *A61B 18/1477* (2013.01); *A61B 18/1492* (2013.01); *A61B 90/39* (2016.02); *A61B 17/320725* (2013.01); *A61B 34/30* (2016.02); *A61B 2017/003* (2013.01); *A61B 2017/00247* (2013.01); *A61B 2017/00309*

**30 Claims, 56 Drawing Sheets**



**Related U.S. Application Data**

(60) Provisional application No. 62/546,247, filed on Aug. 16, 2017, provisional application No. 62/299,963, filed on Feb. 25, 2016.

(51) **Int. Cl.**

*A61B 18/14* (2006.01)  
*A61B 90/00* (2016.01)  
*A61B 34/30* (2016.01)  
*A61B 18/00* (2006.01)  
*A61B 17/00* (2006.01)  
*A61B 17/3207* (2006.01)  
*A61M 39/22* (2006.01)

(52) **U.S. Cl.**

CPC ..... *A61B 2018/00595* (2013.01); *A61B 2018/00601* (2013.01); *A61B 2018/00613* (2013.01); *A61B 2018/1425* (2013.01); *A61B 2018/1475* (2013.01); *A61B 2034/301* (2016.02); *A61B 2034/303* (2016.02); *A61B 2090/066* (2016.02); *A61B 2090/3954* (2016.02); *A61B 2090/3966* (2016.02); *A61M 2039/229* (2013.01)

(56) **References Cited**

U.S. PATENT DOCUMENTS

6,650,923 B1 11/2003 Lesh et al.  
 6,652,491 B1 11/2003 Walker et al.

6,695,814 B2 2/2004 Greene et al.  
 7,056,294 B2 \* 6/2006 Khairkhahan ..... A61B 5/0084  
 600/435  
 8,491,619 B2 \* 7/2013 Breznock ..... A61B 17/00234  
 606/184  
 8,961,550 B2 \* 2/2015 Lenker ..... A61M 25/09041  
 606/185  
 9,445,836 B2 \* 9/2016 Breznock ..... A61B 17/00234  
 9,707,007 B2 \* 7/2017 Lenker ..... A61B 17/3417  
 9,993,266 B2 \* 6/2018 Lenker ..... A61B 17/3478  
 10,034,686 B2 \* 7/2018 Breznock ..... A61B 17/32053  
 10,485,579 B2 \* 11/2019 Lenker ..... A61B 34/30  
 2002/0169377 A1 11/2002 Khairkhahan et al.  
 2007/0021767 A1 1/2007 Breznock  
 2007/0270741 A1 11/2007 Hassett et al.  
 2010/0228276 A1 \* 9/2010 Breznock ..... A61B 17/00234  
 606/185  
 2013/0274784 A1 \* 10/2013 Lenker ..... A61B 17/32053  
 606/185  
 2013/0304106 A1 \* 11/2013 Breznock ..... A61B 17/00234  
 606/170  
 2015/0157353 A1 \* 6/2015 Lenker ..... A61B 17/3417  
 606/185  
 2016/0100860 A1 \* 4/2016 Lenker ..... A61B 17/3478  
 604/95.01  
 2017/0007288 A1 \* 1/2017 Breznock ..... A61B 17/00234  
 2017/0245885 A1 \* 8/2017 Lenker ..... A61B 17/3478  
 2017/0281224 A1 \* 10/2017 Lenker ..... A61B 17/3417  
 2018/0289388 A1 \* 10/2018 Lenker ..... A61B 17/3478  
 2018/0333170 A1 \* 11/2018 Breznock ..... A61B 17/00234  
 2019/0008557 A1 \* 1/2019 Lenker ..... A61B 17/3478

\* cited by examiner




Fig. 1




Fig. 2




Fig. 3




Fig. 4




Fig. 5






Fig. 6






Fig. 8





Fig. 9






Fig. 11




Fig. 12A




Fig. 12B




Fig. 13




Fig. 14




Fig. 15A




Fig. 15B




Fig. 16A




Fig. 16B




FIG. 17A







FIG. 17B






FIG. 19A




FIG. 19B




FIG. 20A




FIG. 20B




FIG. 21A




FIG. 21B




FIG. 22A






FIG. 22B






FIG. 24A







FIG. 24B






FIG. 26A




FIG. 26B




FIG. 27A




FIG. 27B










FIG. 28B



2800














FIG. 34A









FIG. 34B








FIG. 37






FIG. 38






FIG. 40




FIG. 41




FIG. 42A




FIG. 42B




FIG. 43A




FIG. 43B




FIG. 44A




FIG. 44B




FIG. 45




FIG. 46




FIG. 47A






FIG. 47B






FIG. 49A




FIG. 49B




FIG. 49C




FIG. 50A




FIG. 50B




FIG. 50C




FIG. 51A




FIG. 51B




FIG. 52









FIG. 53







## STEERABLE ENDOLUMINAL PUNCH WITH CUTTING STYLET

This application claims priority to U.S. Provisional Application 62/546,247, filed Aug. 16, 2017. This application is a continuation-in-part of U.S. application Ser. No. 15/441,025 filed Feb. 23, 2017, pending, which claims priority to U.S. Provisional Application 62/299,963, filed Feb. 25, 2016.

### FIELD OF THE INVENTIONS

The invention relates to devices and methods for performing endovascular access to the cardiovascular system or other body vessels or body lumens, especially procedures performed in the fields of cardiology, radiology, electrophysiology, and surgery.

### BACKGROUND

The currently accepted procedure for left atrial access involves routing a needle called a Brockenbrough needle into the right atrium with the Brockenbrough needle pre-placed within a guiding catheter. The guiding catheter specifically preferred for use with a Brockenbrough needle is called a Mullins catheter or transseptal introducer. The Brockenbrough needle is a long, small diameter punch, generally formed from a stainless steel wire stylet that is surrounded by a stainless steel tube.

### BRIEF DESCRIPTION OF THE DRAWINGS

FIG. 1 illustrates a side view of a trans-septal punch assembled so that the inner tube is bent in a direction 180 degrees opposite that of the outer tube, resulting in a substantially straight punch configuration, according to an embodiment of the invention;

FIG. 2 illustrates a side view of the disassembled trans-septal punch showing the central core wire or stylet, the inner tube bent in one direction and the outer tube bent in another direction, according to an embodiment of the invention;

FIG. 3 illustrates a side view of the trans-septal punch assembled so that the inner tube bend is aligned in the same direction as the outer tube bend, resulting in a curved distal end on the punch assembly, according to an embodiment of the invention;

FIG. 4 illustrates a side view of a trans-septal punch comprising a flexible region proximal to the distal end and pull-wires disposed between the distal end and the proximal end of the punch, according to an embodiment of the invention;

FIG. 5 illustrates a side view of the trans-septal punch of FIG. 4 wherein one of the pull-wires is placed in tension causing the distal flexible region of the punch to deflect into an arc away from the longitudinal axis of the punch, according to an embodiment of the invention;

FIG. 6 illustrates an adjustable, spacer, which sets and maintains the distance between the distal end of the punch hub and the proximal end of a guide catheter hub, according to an embodiment of the invention;

FIG. 7A illustrates a side, partial breakaway, view of an outer tube of an articulating trans-septal punch comprising a plurality of slots near the distal end to generate a region of increased flexibility, according to an embodiment of the invention;

FIG. 7B illustrates a side, partial breakaway, view of an intermediate, or inner, tube of an articulating trans-septal

punch comprising a longitudinal slot dividing the tube into two axially oriented parts which are connected at the distal end of the inner tube, according to an embodiment of the invention;

FIG. 8 illustrates a cross-sectional view of the proximal end of the articulating trans-septal punch comprising a stopcock and a bend adjusting mechanism, according to an embodiment of the invention;

FIG. 9 illustrates a partial breakaway view of the distal end of the articulating trans-septal punch comprising the outer tube and the inner tube arranged concentrically and oriented circumferentially, according to an embodiment of the invention;

FIG. 10 illustrates an oblique view of the proximal end of the articulating trans-septal punch, according to an embodiment of the invention;

FIG. 11 illustrates a side view of the distal end of the articulating trans-septal punch incorporating a control rod and a control rod retainer, separated from each other, and the outer T-slotted tube with the inner tube being pulled proximally relative to the outer tube causing the outer tube to deform into a curve having very stiff, or rigid, mechanical properties, according to an embodiment of the invention;

FIG. 12A illustrates a top view of a portion of the distal flexible region of an outer tube comprising dovetails or interlocking grooves to reduce torque or side-to-side motion, according to an embodiment of the invention;

FIG. 12B illustrates a side view of a portion of the outer tube distal flexible region of an outer tube comprising dovetails or locking grooves to reduce torque or side-to-side motion, according to an embodiment of the invention;

FIG. 13 illustrates the distal end of an articulating septal punch advanced nearly to the distal end of an obturator or dilator, which is coaxially, removably assembled into the central lumen of a guide catheter sheath, according to an embodiment of the invention;

FIG. 14 illustrates the distal end of an articulating trans-septal punch further comprising a removable obturator having a collapsible distal shield, according to an embodiment of the invention;

FIG. 15A illustrates an outer tube cut in its flexible regions with shorter lateral slots and with reduced or complete elimination of some T-slots to improve resistance to bending in that region, according to an embodiment of the invention;

FIG. 15B illustrates a control rod without any control rod retainer leaving only the c-shaped control rod and the distal end, according to an embodiment of the invention;

FIG. 16A illustrates a cross-sectional view of a control rod configuration in a steerable transseptal punch within the flexible region, wherein the separation between the control rod and a control rod retainer is substantially at the midpoint or center of the outer tube, according to an embodiment of the invention;

FIG. 16B illustrates a lateral cross-section of a tubing configuration of a steerable transseptal punch within the flexible distal region, with an off-center slot, according to an embodiment of the invention;

FIG. 17A illustrates a cross-sectional view of a steerable transseptal punch comprising an outer tube and three control rods, each subtending approximately  $\frac{1}{3}$  of the internal circumference of the outer tube, some or all of which can be functional and each of which is separated from the other by the spacing and all residing within the central lumen of the outer tube, according to an embodiment of the invention;

FIG. 17B illustrates a cross-sectional view of a steerable transseptal punch comprising an outer tube and four control

3

rods, each subtending approximately  $\frac{1}{4}$  of the internal circumference of the outer tube, some or all of which can be functional and each of which is separated from the other by the spacing and all residing within the central lumen of the outer tube, and further including an innermost tube to control the fluid path and prevent ingress of egress of fluid from the central lumen of the punch assembly, according to an embodiment of the invention;

FIG. 18A illustrates a lateral cross-section of a steerable transseptal punch comprising an outer tube, a control rod, a control rod retainer, an internal pressure sleeve to prevent ingress or egress of fluids, and a stylet, according to an embodiment of the invention;

FIG. 18B illustrates a lateral cross-section of a steerable transseptal punch comprising an outer tube, two control rods subtending  $\frac{1}{2}$  of the internal circumference of the inner lumen and a control rod retainer subtending  $\frac{1}{2}$  of the internal circumference of the outer tube, along with a central stylet, according to an embodiment of the invention;

FIG. 18C illustrates a side view of a control rod and keeper system comprising a c-shaped control rod and a c-shaped control rod guide, retainer, or keeper configured to maintain the control rod against the inside diameter of an outer tube and further comprising ends configured for welding and providing a fluid-tight seal with other structures within a punch, according to an embodiment of the invention.

FIG. 19A illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube and a control rod in the shape of a "V" or "L", according to an embodiment of the invention;

FIG. 19B illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube and a control rod in the shape of an open ended box or "U", according to an embodiment of the invention;

FIG. 20A illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube and two hollow control rods, each of which having a circular cross-section, according to an embodiment of the invention;

FIG. 20B illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube, two hollow control rods, and a stylet, each of which comprising a circular cross-section, according to an embodiment of the invention;

FIG. 21A illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube, a rectangular control rod with rounded ends and a round stylet within a lumen of the control rod, according to an embodiment of the invention;

FIG. 21B illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube and an I-beam shaped control rod, according to an embodiment of the invention;

FIG. 22A illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen and a control rod disposed within the central lumen, according to an embodiment of the invention;

FIG. 22B illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube, a hollow control rod disposed within the lumen of the outer tube, and a stylet disposed within the lumen of the control rod, according to an embodiment of the invention;

FIG. 23A illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen and a control rod disposed within the central lumen, the control rod having a central lumen and two channels to

4

retain the one or more control wires or rods, according to an embodiment of the invention;

FIG. 23B illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube, a control rod, and a control rod guide, the guide and the control rod being separated by slots formed at an angle other than radial, according to an embodiment of the invention;

FIG. 24A illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen, a control rod disposed within the central lumen of the outer tube, the control rod having a central lumen and subtending less than a full circle circumferentially, and a central stylet, according to an embodiment of the invention;

FIG. 24B illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube, a c-shaped control rod, and a control rod guide having thinner wall than the control rod, the guide and the control rod being separated by slots formed radially, according to an embodiment of the invention;

FIG. 25A illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen, a c-shaped control rod disposed within the central lumen of the outer tube, a c-shaped control rod retainer, and narrow slots separating the control rod and the retainer, according to an embodiment of the invention;

FIG. 25B illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen, a c-shaped control rod disposed within the central lumen of the outer tube, a c-shaped control rod retainer, and medium width slots separating the control rod and the retainer, according to an embodiment of the invention;

FIG. 25C illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen, a c-shaped control rod disposed within the central lumen of the outer tube, a c-shaped control rod retainer, extremely wide slots separating the control rod and the retainer, and a large gap between the OD of the control rod and retainer and the ID of the outer tube, according to an embodiment of the invention;

FIG. 26A illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen, a plurality of control rods or wires, an inner tube, and a central stylet, according to an embodiment of the invention;

FIG. 26B illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen, a plurality of hollow tubular control rods or wires, an inner tube, and a central stylet, according to an embodiment of the invention;

FIG. 27A illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen and a solid central control rod slidably disposed therein, according to an embodiment of the invention;

FIG. 27B illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen, a semi-circular first solid control rod, and a semi-circular solid control rod retainer or second control rod, according to an embodiment of the invention;

FIG. 28A illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen and a plurality of radially oriented cuts or grooves disposed in two generally orthogonal directions, the different cuts or grooves being interdigitated between each other along the length of a flexible region, a plurality of control rods and a control rod retainer, according to an embodiment of the invention;

5

FIG. 28B illustrates a lateral cross section of the steerable transseptal punch comprising an outer tube having a central lumen, two quarter-circular arcuate control rods, and a semi-circular hollow control rod retainer, according to an embodiment of the invention;

FIG. 29A illustrates a lateral cross section of a steerable transseptal punch comprising an outer tube having a central lumen and a plurality of radially oriented cuts or grooves disposed in two generally orthogonal directions, the different cuts or grooves being placed in order with the grooves in the first direction in a different axial region of the tube than the grooves in the second direction and each defining a flexible region in a specific direction, a plurality of control rods, a plurality of distal weld points, and a control rod retainer, according to an embodiment of the invention;

FIG. 29B illustrates a lateral cross section of the steerable transseptal punch comprising an outer tube having a central lumen, two quarter-circular arcuate control rods, and a semi-circular hollow control rod retainer, according to an embodiment of the invention;

FIG. 30A illustrates a lateral cross section of a steerable transseptal needle comprising an outer tube having a central lumen and a plurality of radially oriented openings, cuts, or grooves disposed in a single direction, defining a flexible region in a specific direction, a hollow circular control rod, a distal weld point between the control rod and the outer tube, a pressure jacket over the openings in the outer tube to prevent fluid leakage or ingress, and a distal hinge on the control rod, according to an embodiment of the invention;

FIG. 30B illustrates a lateral cross section of the steerable transseptal punch comprising an outer tube having a central lumen and a hollow circular, tubular control rod having a central lumen, according to an embodiment of the invention;

FIG. 31A illustrates a side view of a steerable transseptal needle comprising a blunt distal end and a sharp, tissue piercing stylet or obturator, in its retracted state, according to an embodiment of the invention;

FIG. 31B illustrates a side view of the steerable transseptal needle of FIG. 31A with the sharp stylet or obturator advanced distally beyond the distal end of the inner tube to form a sharp, tissue punch, according to an embodiment of the invention;

FIG. 32A illustrates a steerable transseptal needle comprising a radiopaque marker at the distal end of the inner tube as well as a small diameter segment of the stylet wire, according to an embodiment of the invention;

FIG. 32B illustrates the steerable transseptal needle of FIG. 32A with the stylet advanced out the distal end of the inner tube, according to an embodiment of the invention;

FIG. 33A illustrates a steerable transseptal needle comprising a beveled tip, sharp stylet, according to an embodiment of the invention;

FIG. 33B illustrates the steerable transseptal needle of FIG. 33A with the beveled sharp stylet advanced out the distal end of the inner tube;

FIG. 34A illustrates a hub configured for use with a piercing stylet or obturator in its retracted state, according to an embodiment of the invention;

FIG. 34B illustrates the hub of FIG. 34A actuated such that the stylet or obturator is advanced a controlled distance, according to an embodiment of the invention;

FIG. 35A illustrates a side exterior view of a stylet hub further comprising a removable safety clip, according to an embodiment of the invention;

FIG. 35B illustrates the hub of FIG. 35A in oblique view, according to an embodiment of the invention;

6

FIGS. 36A, 36B and 36C illustrate a side view of a steerable transseptal needle with a piercing stylet hub removably affixed to the proximal end of the needle hub, according to an embodiment of the invention;

FIG. 37 illustrates a top view of a steerable transseptal needle comprising a three-way stopcock affixed to its hub, rather than the standard one-way stopcock, according to an embodiment of the invention;

FIG. 38 illustrates a faceted sharp distal end of a piercing stylet, according to an embodiment of the invention;

FIG. 39A illustrates a side, partial breakaway view of the distal end of a steerable transseptal needle wherein a portion of the stylet shaft has been cut away to facilitate fluid flow within the central lumen of the steerable transseptal needle, according to an embodiment of the invention;

FIG. 39B illustrates a lateral cross-section of a stylet wire configured to facilitate fluid flow or pressure measurement while the stylet wire is in place within the steerable transseptal needle lumen, according to an embodiment of the invention;

FIG. 40 illustrates a hub of a steerable transseptal needle safety piercing stylet wherein the hub comprises magnetic latches to actuate the stylet, according to an embodiment of the invention;

FIG. 41 illustrates the hub of a steerable medical device wherein the hub comprises two separate jackscrews, affixed to separate control rods, and moving axially in opposite directions under the control of a knob and an optional stepper motor, according to an embodiment of the invention;

FIG. 42A illustrates a steerable needle or medical device, in its straightened configuration, comprising two regions of flexibility separated by a non-flexible segment, according to an embodiment of the invention;

FIG. 42B illustrates the steerable needle or medical device of FIG. 42A in a curved or articulated orientation, according to an embodiment of the invention;

FIG. 43A illustrates a side view, in partial cutaway, of the distal end of a steerable needle further comprising a stylet that is configured to cut tissue but with the cutting element retracted, according to an embodiment of the invention;

FIG. 43B illustrates a side view, in partial cutaway, of the distal end of the steerable needle further comprising the cutting stylet as shown in FIG. 43A but with the cutting element of the stylet actuated so as to project radially outward, according to an embodiment of the invention;

FIG. 44A illustrates a side view, in partial cutaway, of the distal end of a steerable needle further comprising a cutting stylet comprising a window and a plurality of retracted expandable blades, according to an embodiment of the invention;

FIG. 44B illustrates a side view, in partial cutaway, of the distal end of the steerable transseptal needle of FIG. 44A with the plurality of cutting blades radially expanded, according to an embodiment of the invention;

FIG. 45 illustrates a side view of the distal end of a steerable transseptal needle comprising a cutting stylet wire that is split into two blades biased radially outward so as to project laterally when the stylet wire is exposed beyond the end of the steerable transseptal needle, according to an embodiment of the invention;

FIG. 46 illustrates the proximal end of a steerable transseptal needle with a hub, wherein the hub includes a radiofrequency generator, a power supply, and a switch to actuate the system, according to an embodiment of the invention;

FIG. 47A illustrates the distal end of a piercing stylet for use with a transseptal needle, wherein the piercing stylet

comprises a hollow tubular construction to permit flow therethrough as well as a radiopaque marker positioned near the distal tip of the stylet, according to an embodiment of the invention;

FIG. 47B illustrates the proximal end of the piercing stylet of FIG. 47A, showing the hollow tubular structure and a window disposed near the proximal end to allow for infusion or withdrawal of fluids within the hollow tubular structure, according to an embodiment of the invention

FIG. 48A illustrates a side partial cross-sectional view of the proximal end of a steerable transseptal needle with a side port and a disengaging jackscrew traveler, according to an embodiment of the invention;

FIG. 48B illustrates a view of the proximal end of the steerable transseptal needle of FIG. 48A, according to an embodiment of the invention;

FIG. 49A illustrates a side, partial cutaway view of an introducer sheath comprising a window in its side wall proximate the distal end and further comprising a window in the side wall of the dilator in the same region as the window in the side wall of the introducer, according to an embodiment of the invention;

FIG. 49B illustrates a side view of the punch system wherein an articulating endoluminal punch, in its straightened configuration, has been advanced such its distal end and articulating portion are aligned with the side windows of the sheath and dilator, according to an embodiment of the invention;

FIG. 49C illustrates a view of the punch system of FIG. 49B wherein the punch has been articulated sideways through the side window, further wherein the support structure provides backup support for the punch to allow lateral force to be applied to tissue being incised, according to an embodiment of the invention;

FIG. 50A illustrates a steerable endoluminal punch having a distal end that can be reconfigured from a first, more blunted or atraumatic shape (as illustrated) into a second shape, which is configured to be sharper and more capable of cutting tissue, according to an embodiment of the invention;

FIG. 50B illustrates the reconfigurable distal end of the steerable endoluminal punch with its distal end having been reconfigured into a sharper shape, according to an embodiment of the invention;

FIG. 50C illustrates the punch of FIG. 50B wherein the stylet control rod has been advanced distally;

FIG. 51A illustrates the distal end of a steerable endoluminal punch comprising a conic section; according to an embodiment of the invention;

FIG. 51B illustrates the distal end of a steerable endoluminal punch which includes the conic section of FIG. 51A combined with a bevel to create a sharp edge that is displaced radially inward from the outer diameter of the steerable endoluminal punch, according to an embodiment of the invention;

FIG. 52 illustrates the distal end of a steerable endoluminal punch comprising a blunted stylet that protects the walls of a catheter from the sharp edge of the endoluminal punch, according to an embodiment of the invention;

FIG. 53 illustrates a steerable endoluminal punch being used to access the fossa ovalis of the heart by way of a superior approach through the superior vena cava and an access point cranial to the superior vena cava, according to an embodiment of the invention;

FIG. 54A illustrates a steerable endoluminal punch having a 4-pointed crown-shaped sharp distal end configured to

penetrate tissue with and without the use of a central punch, according to an embodiment of the invention; and

FIG. 54B illustrates a steerable endoluminal punch having a two-point crown-shaped sharp distal end configured to penetrate tissue with and without the use of a central punch, according to an embodiment of the invention.

FIG. 55 illustrates the distal end of a steerable endoluminal punch system comprising a cutting stylet with laterally biased cutting blades.

FIGS. 56A and 56B illustrate a cutting introducer.

## DETAILED DESCRIPTION

In accordance with current terminology pertaining to medical devices, the proximal direction will be that direction on the device that is furthest from the patient and closest to the user, while the distal direction is that direction closest to the patient and furthest from the user. These directions are applied along the longitudinal axis of the device, which is generally an axially elongate structure having one or more lumens or channels extending through the proximal end to the distal end and running substantially the entire length of the device.

In an embodiment, the punch comprises an inner core wire or stylet, an inner tube and an outer tube. In an embodiment, the stylet can be removable or non-removable. The punch further comprises a hub at its proximal end which permits grasping of the punch and also includes a stopcock or valve to serve as a lock for the stylet, or inner core wire, as well as a valve for control of fluid passage into and out from the innermost lumen within which the stylet or inner core wire resides. The proximal end further comprises one or more control handles to manipulate the amount of articulation at the distal end of the catheter. The proximal end further is terminated with a female Luer or Luer lock port, which is suitable for attachment of pressure monitoring lines, dye injection lines, vacuum lines, a combination thereof, or the like.

In another embodiment, steerability can be obtained using actuators on the surface or within the interior of the cannula to force bending of the cannula. These actuators can be typically electrically powered. In an embodiment, an actuator can comprise electrical leads, a power source, a compressible substrate, and shape memory materials such as nitinol. Such actuators may be distributed along the length of the cannula. The actuators may be placed so as to oppose each other. Opposing actuators are activated one at a time and not simultaneously and can generate a steering effect or back and forth motion.

Other embodiments of the inventions comprise methods of use. One method of use involves inserting the central core wire or stylet so that it protrudes out the distal end of the punch. A percutaneous or cutdown procedure is performed to gain access to the vasculature, either a vein or an artery. An introducer and guidewire are placed within the vasculature and the guidewire is routed proximate to the target treatment site. The introducer can be removed at this time. A guiding catheter, preferably with a removable central obturator or dilator, with a tapered distal tip pre-inserted, is routed over the guidewire to the target site. In some embodiments, the guide catheter is routed through from a femoral vein, through the inferior vena cava, and into the right atrium of the heart. In an embodiment, the target site can be the atrial septum of the heart in the region of the Fossa Ovalis. In some embodiments, the guide catheter distal tip is routed past the right atrium and into the superior vena cava. The guidewire can be removed at this time. The punch is adjusted

so that it assumes a substantially straight configuration. The punch can be advanced through the central lumen of the already placed catheter, sheath, introducer, or guide catheter. By making the punch as straight as possible, there is no curvature to force the sharpened distal edges of the punch to scrape the inside of the catheter lumen as the punch is advanced distally inside the guide catheter and potentially dislodge or skive away debris or material which could cause embolic effects to the patient. Carefully ensuring that the punch does not protrude beyond the distal end of the catheter or its obturator, the punch is next deflected so that it forms a curve. The distal end of the punch is sufficiently radiopaque that it is observable clearly under fluoroscopy or X-ray imaging. The location of the punch and the amount of deflection and curvature of the distal end are observed and controlled using the aforementioned fluoroscopy or X-ray imaging, or other imaging method such as MRI. The curve is oriented so that it is medially directed toward the atrial septum. Alignment with any curvature of the catheter can be completed at this time. The punch and guide catheter/obturator are withdrawn caudally, as a unit, into the right atrium from the superior vena cava. The punch and guide catheter are positioned using fluoroscopy or other imaging system against the Fossa Ovalis. The Fossa Ovalis is a relatively thin structure and the force of the punch will tent the Fossa Ovalis toward the left atrium. In one embodiment, the central core wire or stylet, initially advanced, can next be withdrawn to expose the sharp distal edge of the punch. When correctly positioned under fluoroscopy, ultrasound, or other imaging system, dye can be injected into the central lumen of the punch at its proximal end and be expelled out of the distal end of the punch and obturator to paint or mark the Fossa Ovalis. A generally "V-shaped" mark can be observed under fluoroscopy, which denotes the location of the Fossa Ovalis. The curvature of the punch can be increased or decreased by articulation to gain optimal alignment with the Fossa Ovalis. This steering function can be very beneficial in device placement.

Maintaining the position of the guiding catheter against the Fossa Ovalis, the punch is advanced distally against and through the atrial septum, in the region of the Fossa Ovalis, so that it penetrates and protrudes into the left atrium. In order to stabilize the atrial septal tissue prior to coring, a distally protruding corkscrew tipped wire or a vacuum head operably connected to the proximal end of the punch, can be used to grasp and retract the septal tissue. Once the initial penetration is completed, the guide catheter is next advanced, with its tapered obturator leading the way, across the atrial septum until it resides within the left atrium. The tapered obturator or dilator along with the punch can be removed at this time to allow for catheter placement through the guiding catheter. In another embodiment, a calibrated spacer can be used between the guide catheter hub and the punch hub to ensure that the punch does not protrude beyond the distal end of the guide catheter tip until the desired time for punching the hole. At this point, the spacer is unlocked and removed from the punch or catheter. In some embodiments, the punch is removed from the guide catheter and the same punch is routed through a second guide catheter to provide access to the left atrium for the second guide catheter. Two guide catheters are often necessary for ablation procedures because one guide catheter is used to route mapping and diagnostic devices into the left atrium while the second guide catheter is used to route therapeutic catheters into the left atrium. Thus, the punch can be used more than once on a given patient but, for prevention of contamination, the same punch should not be used on different

patients because cleaning and sterilization after use is nearly impossible given the small distances between the moving inner and outer tubes which can hide contamination from cleaning or sterilization by the user.

In another embodiment, the core wire, obturator or stylet is sharpened and serves as a tissue punch. In this embodiment, the distal end of the hollow tubes of the punch are blunted and made relatively atraumatic. Once the core wire punch has completed tissue penetration, the outer tubes are advanced over the central punch wire through the penetration and into the left atrium. In another embodiment, a pressure monitoring device such as a catheter tip pressure transducer, or a pressure line terminated by a pressure transducer, can be affixed to a quick connect, generally a Luer fitting, at the proximal end of the punch hub. By monitoring pressure, it is possible to determine when the distal end of the punch has passed from, for example, the right atrium into the left atrium, because the pressure versus time curves in these two chambers are measurably, or visually, different. The proximal end of the hub further has provision for attachment to a dye injection line for use in injecting radiographic contrast media through the central lumen of the punch. Typically a manifold can be attached to the Luer fitting on the proximal end of the hub, the manifold allowing for pressure monitoring, for example on a straight through port, and for radiopaque dye injection, for example through a side port. A stopcock, or other valve, can be used to control which port is operably connected to the central lumen of the punch.

In some embodiments, the inner tube, the outer tube, or both can have slots imparted into their walls to impart controlled degrees of flexibility. The slots can be configured as "snake cuts" to form a series of ribs with one or more spines. The spines can be oriented at a given circumferential position on the outer tube, the inner tube, or both. The spines can also have non-constant orientations. In some embodiments, only the outer tube is slotted. The slots can be generated within the distal portion of the outer tube where the curve is generated. This distance can range between 3-cm and 15-cm of the end and preferably between 7-cm and 12-cm of the distal end. The slot widths can range between 0.001 inches and 0.100 inches with a preferable width of 0.003 to 0.025 inches. In exemplary embodiments, the slot widths are about 0.010 inches. In some embodiments, it is desirable to have the outer tube bend in one direction only but not in the opposite direction and not in either lateral direction. In this embodiment, cuts can be made on one side of the outer tube within, for example, the distal 10-cm of the tube length. Approximately 10 to 30 cuts can be generated with a width of approximately 0.010 to 0.040 inches. The cut depth, across the tube diameter from one side, can range between 0.1 and 0.9 of the tube diameter. In an embodiment, the cut depth can be approximately 0.4 to 0.6 of the tube diameter with a cut width of 0.025 inches. A second cut can be generated on the opposite side of the tube wherein the second cut is approximately 0.005 inches or less. In an embodiment, the outer tube can be bent into an arc first and then have the slots generated such that when the tube is bent back toward the 0.005 inch wide cuts, the tube will have an approximately straight configuration even through each tube segment between the cuts is slightly arced or curved.

FIG. 1 illustrates a side view of a punch, needle, or catheter assembly **100**, with an integral articulating or bending mechanism. The punch assembly **100** comprises a stylet or obturator wire **102**, an inner tube **104**, an outer tube **106**,

11

an obturator grasping tab **108**, a stopcock **110**, an inner tube pointer **112**, an outer tube pointer **114**, an inner tube hub **116**, and an outer tube hub **118**.

Referring to FIG. 1, the obturator wire **102** is affixed to the obturator grasping tab **108**. The stylet or obturator wire **102** is inserted through the central lumen of the inner tube **104** and is slidably disposed therein. The stopcock **110** is affixed to the inner tube hub **116** and the through lumen of the stopcock **110** is operably connected to the central lumen of the inner tube **104**. The inner tube pointer **112** is affixed to the inner tube hub so that it is visible to the user. The outer tube pointer **114** is affixed to the outer tube hub **118** so that it is visible to the user. The inner tube hub **116** and the inner tube **104** are able to rotate about the longitudinal axis within the outer tube hub **118** and the outer tube **106**. In an embodiment, the inner tube **104** is restrained from longitudinal motion relative to the outer tube **106**. In this embodiment and other embodiments in which the inner tube is fixed to the outer tube, the inner tube may be longitudinally fixed to the outer tube at a point distal to the "flexible region" of the outer tube, but not longitudinally fixed to the outer tube at any point proximal to the "flexible region" so that the inner tube and outer tube can be tensioned relative to each other to affect bending of the "flexible region." In another embodiment, the inner tube **104** can be advanced distally relative to the outer tube **106**. In this latter embodiment, advancement of the inner tube **104** can be used to facilitate punching. The distal end of the inner tube **104** can be sharpened and serve as a punch. The distal end of the inner tube **104** is sheathed inside the outer tube **106** to protect the tissue from the sharp distal edge of the inner tube **104** until the inner tube **104** is advanced distally outside the distal end of the outer tube **106**. A releasable lock can be used to maintain the axial or longitudinal position of the inner tube **104** relative to the outer tube **106** until punching is required. A releasable lock can further be used to maintain the rotational position of the inner tube hub **116** and thus the inner tube **104** relative to the outer tube hub **118** and the outer tube **106**.

All components of the punch assembly **100** can be fabricated from metals such as, but not limited to, stainless steel, Elgiloy™, cobalt nickel alloy, titanium, nitinol, or the like. The nitinol can be shape-memory or it can be super-elastic. The metals used in the obturator wire **102**, the inner tube **104** and the outer tube **106** are advantageously cold rolled, heat treated, or otherwise processed to provide a full spring hardness. The inner tube **104**, the outer tube **106**, or both, are relatively rigid, resilient structures. Polymeric materials, such as, but not limited to, polycarbonate, ABS, PVC, polysulfone, PET, polyamide, polyimide, and the like, can also be used to fabricate the stopcock **110**, the inner tube hub **116**, the outer tube hub **118**, the inner tube pointer **112**, and the outer tube pointer **114**. The materials are beneficially radiopaque to maximize visibility under fluoroscopy during the procedure. Additional radiopaque markers fabricated from tantalum, platinum, iridium, barium sulfate, and the like can be added to improve visibility if needed. The inner tube **104** is curved or bent near its distal end into a gentle curve, preferably with a radius of between 1 to 5 inches and so that the distal tip is deflected through an angle of approximately 10 to 90 degrees from the longitudinal axis of the inner tube **104**. The outer tube **106** is curved or bent near its distal end into a gentle curve, preferably with a radius of between 1 to 5 inches and so that the distal tip is deflected through an angle of approximately 10 to 90 degrees from the longitudinal axis of the outer tube **106**. The inner tube hub **116** is welded, silver soldered, bonded, crimped, or other-

12

wise fastened to the proximal end of the inner tube **104** so that the inner tube pointer **112** points in the direction of the bend in the inner tube **104**. The outer tube hub **118** is welded, silver soldered, bonded, crimped, or otherwise fastened to the proximal end of the outer tube **106** so that the outer tube pointer **114** points in the direction of the bend in the outer tube **106**. When the inner tube pointer **112** is oriented 180 degrees away from the direction of the outer tube pointer **114**, the bend in the inner tube **104** substantially counteracts or opposes the bend of the outer tube **106** and the coaxial assembly **100** is substantially straight, as shown in FIG. 1. The stopcock **110** can also be a ring seal, Tuohy-Borst valve, membrane valve, hemostasis valve, gate valve, or other valve, generally, but not necessarily manually operated. The stiffness of the inner tube **104** and the outer tube **106** are sufficient that the punch can be used as a guide for other catheters through which the punch **100** is passed and will deflect those catheters, even ones that have thick walls and high resistance to bending.

FIG. 2 illustrates a side view of a stylet or obturator **140** further comprising the obturator wire **102** and the obturator-grasping tab **108**. The obturator wire **102** is blunted at its distal end to render it as atraumatic as possible. In another embodiment, the obturator wire **102** can be tapered in diameter to render it very flexible and therefore atraumatic at its distal end. The obturator wire **102**, in another embodiment, can be sharpened and serve as a needle or primary punching mechanism. FIG. 2 also illustrates an intermediate punch assembly **120** further comprising the inner tube **104**, the stopcock **110**, the inner tube pointer **112**, the inner tube hub **116**, an inner tube seal **124**, an inner tube pointer ball **126**, a through lumen port **128**, a beveled distal tip **132**, and a pre-set curve **136**. FIG. 2 further illustrates an outer tube assembly **122** further comprising the outer tube **106**, the outer tube hub **118**, the outer tube pointer **114**, an outer tube distal curve **130**, and an outer tube pointer ball **134**.

Referring to FIG. 2, the obturator-grasping tab **108** is affixed, either integral to, silver soldered, welded, crimped, adhered, pinned, or otherwise attached, to the proximal end of the obturator wire **102**. The inner tube **104** is affixed to the inner tube hub **116** by silver soldering, welding, potting, crimping, setscrew, pin, or other fixation method, such that the hub **116** rotates 1 to 1 with the inner tube **104**. An optional inner tube pointer ball **126** is affixed to the inner tube pointer **112** and provides additional visual and tactile rotational positioning sense for the intermediate punch or needle assembly **120**. A curve or bend **136** is heat set, or cold worked into the inner tube **104** at or near its distal end. The distal end of the inner tube **104** comprises a bevel **132** which helps serve as a punch or cutting edge for the inner tube **104**. The angle of the bevel **132** can range between 20 and 70 degrees from the direction perpendicular to the longitudinal axis of the inner tube **104**. In another embodiment, the bevel is removed and the distal tip of the inner tube **104** is a gentle inward taper or fairing moving distally that serves as a dilator should the obturator wire **102** be used as the punching device rather than the blunt distal tip obturator of the inner tube **104**.

In yet another embodiment, the distal tip can comprise a conic section that can be further beveled. For example a 5 degree conic can be applied to the distal tip of the inner tube such that a very thin flat edge exists at the distal tip. This cone angle can range between about 1-degree to about 10-degrees. This flat edge can be beneficially set at between 0.001 and 0.005 inches with a preferred dimension of between 0.001 and 0.003 inches. This distal tip can then be further beveled to create a controlled amount of sharpness.

In certain embodiments, the wall thickness of the tubing ranges from about 0.002 to 0.010 inches with a preferred range of about 0.003 and 0.007 inches. The conic section moves the sharp region of the distal tip radially inward so that it is not directly at the exterior of the tube and thus, the inner tube distal end is less likely to scrape on the interior walls of any catheters through which it is inserted. The heel or most proximal part of the beveled tubing can further be buffed or rounded to minimize sharpness at that location. The other edges of the beveled end, other than at the pointed tip can also be beveled to reduce sharpness in all areas except for the distal most portion of the bevel.

The inner tube hub **116** further comprises a circumferential groove with an "O" ring **124** affixed thereto. The "O" ring **124** serves to form a fluid (e.g. air, blood, water) tight seal with the inner diameter of the outer sheath hub **118** central lumen and allows for circumferential rotation of the inner tube hub **116** within the outer tube hub **118**. The "O" ring **124** can be fabricated from rubber, silicone elastomer, thermoplastic elastomer, polyurethane, or the like and may be lubricated with silicone oil or similar materials. The stopcock **110** can be a single way or a three-way stopcock without or with a sideport, respectively.

The outer punch assembly **122** comprises the bend **130**, which is heat set or cold worked into the outer tube **106** in the same longitudinal location as the bend **136** of the inner tube. The wall thicknesses of the inner tube **104** and the outer tube **106** are chosen to provide bending forces that cancel out when the curves **136** and **130** are oriented in opposite directions and the inner tube **104** is inserted fully into the outer tube **106**. The wall thickness of the outer tube **106** and the inner tube **104** can range between 0.003 inches and 0.20 inches, preferably ranging between 0.004 and 0.010 inches. The outer diameter of the outer tube **106** can range between 0.014 and 0.060 inches and preferably between 0.025 and 0.050 inches. In a most preferred embodiment, the outside diameter of the outer tube **106** is about 0.048 inches. The outer diameter of the obturator wire **102** can range between 0.005 and 0.030 inches and preferably range between 0.010 and 0.020 inches.

FIG. 3 illustrates a side view of the punch assembly **100** fully assembled and aligned so that both the inner tube distal curve **136** (Refer to FIG. 2) and the outer tube distal curve **130** are aligned in the same direction resulting in a natural bend out of the axis of the punch **100**. The punch assembly **100** comprises the obturator wire **102**, the inner tube **104**, the outer tube **106**, the obturator grasping tab **108**, the stopcock **110**, the inner tube pointer **112**, the outer tube pointer **114**, the inner tube hub **116**, the inner tube pointer ball **126**, and the outer tube pointer ball **134**.

Referring to FIG. 3, the outer tube pointer **114** and inner tube pointer **112** are aligned together and in this configuration, the tubing assembly possesses its maximum curvature, which is oriented in the same directions as the pointers **112** and **114**. The pointer balls **126** and **134** are aligned together to provide additional tactile and visual indices of curvature direction. In an embodiment, the curvature of the tube assembly **104** and **106** is unbiased with no net force exerted therebetween and an angle of approximately 45 degrees is subtended by the device in the illustrated configuration. Further curvature can also occur out of the plane of the page so that the curvature takes on a 3-dimensional shape, somewhat similar to a corkscrew. In another embodiment, the curvature of the aligned inner tube **104** and the outer tube **106** subtends an angle of 90-degrees or greater. Again, the inner tube **104** and the outer tube **106** have stiffness sufficient that the assembly is capable of guiding any catheter

through which the punch **100** is passed. In another embodiment, the inner tube **104** and the outer tube **106** have different degrees of curvature so that when they are aligned, a net force still is generated between the two tubes, although a maximum curvature configuration is still generated. This embodiment can be advantageous in permitting articulation in a direction away from the direction of primary curvature. The radius of curvature of the punch **100** can range from substantially infinity, when straight, to as little as 0.5-cm, with a preferred range of infinity to as little as 2-cm radius when fully curved or articulated. One embodiment permits a substantially infinite to a 3-cm radius of curvature. The overall working length of the punch, that length from the proximal end of the outer tube hub to the distal most end of the punch, can range from 10 to 150-cm and preferably between 60 and 100-cm, with a most preferred range of between 70 and 90-cm. A preferred curve has a radius of about 3-cm and is bent into an arc of about 45 to 90 degrees.

FIG. 4 illustrates a side view of another embodiment of a needle or punch assembly **400** comprising an obturator wire **102**, an obturator wire grasping tab **108**, a stopcock **110**, an inner tube **404**, an outer tube **406**, a plurality of deflecting wires **412**, an outer tube hub **414**, a deflecting lever **416**, a weld **420**, an axis cylinder **424**, a plurality of deflecting wire channels **426**, and a flexible region **430**. The distal end of the region just proximal to the flexible region **430** is shown in breakaway view. Furthermore, the distal end of the region just proximal to the flexible region **430** as well as the flexible region **430** has been expanded in scale so that certain details are more clearly visible.

Referring to FIG. 4, the flexible region **430** is affixed to the outer tube **406** by a weld **420**. The flexible region **430** can also be fixed to the outer tube **406** by a crimp, pin, setscrew, adhesive bond, interference fit, mechanical interlock, thread, or the like. The attachment between the flexible region **430** and the outer tube **406** is made at the proximal end of the flexible region **430** and a second attachment or weld **420** can be made at the distal end of the flexible region **430** so as to attach to a length of distal outer tube **406**. The flexible region **430** can comprise a length of coiled wire such as that used in guidewires, it can be a tube that comprises cutouts to provide a backbone configuration to impart flexibility, it can be a length of polymeric tube with elastomeric characteristics, or it can be another type of structure that is known in the art as providing flexibility. These preferred structures also advantageously provide column strength and kink resistance to the flexible region **430**. The center of the flexible region **430** is hollow and comprises a lumen, which is operably connected to the central lumen of the outer tube **406** at both the proximal and distal end of the flexible region **430**. The stopcock **110** is affixed, at its distal end, to the outer tube hub **414**. The outer tube hub **414** further comprises a deflecting lever **416** that is affixed to the axis cylinder **424**, which serves as an axle or rotational pin, and can be moved proximally or distally by manual action on the part of the operator or by a motor or other electromechanical actuator (not shown). The deflecting lever **416** is operably connected to the proximal ends of the deflecting wires **412**. In an exemplary embodiment, one of the deflecting wires **412** is affixed to the top of the axis cylinder **424** and the other deflecting wire is affixed to the bottom of the axis cylinder **424**. When the deflecting lever is pulled proximally, for example, the top wire **412** is placed under tension and the tension on the bottom wire is relieved causing tension to be exerted on the distal end of the punch **400**. The deflecting wires **412** are slidably routed through the deflecting wire channels **420** within the outer tube **406**. The deflecting wires

412 also run through the deflecting wire channels 420 within the flexible region 430. The deflecting wires 412 can also be routed through the internal lumen of the outer tube 406 and the flexible region 430.

Referring to FIG. 4, the outer tube hub 414 is affixed to the proximal end of the outer tube 406 by a crimp, pin, setscrew, adhesive bond, interference fit, mechanical interlock, thread, or the like. The inner tube 404 is affixed to the distal end of the outer tube 406 by a crimp, pin, setscrew, adhesive bond, interference fit, mechanical interlock, thread, or the like. In another embodiment, the inner tube 404 is routed throughout the length of the outer tube 406. In this embodiment, the inner tube can comprise grooves (not shown) that serve as deflecting wire channels 420 when the inner tube 404 is inserted inside the outer tube 406. Such grooves can also be disposed on the interior surface of the outer tube 406, rather than on the exterior surface of the inner tube 404. The obturator wire 102 and the attached grasping loop 108 are slidably disposed within the inner lumen of the outer tube 406, or the inner tube 404. The inner tube 404 is gently tapered up to the outer tube 406 at the distal end of the outer tube 406 in a transition region so that a dilator effect can be created during distal advancement of the punch 400. The distal end of the inner tube 404 can comprise a bevel 132 (FIG. 2) or other sharp point for punching through biological tissue. The distal end of the inner tube 404 preferably forms a non-coring needle or punch that does not excise a tissue sample. The non-coring punch feature is achieved by keeping the central lumen closed or very small. The non-coring punch 400 embodiment can comprise filling the lumen of the inner tube 404 with the obturator or stylet wire 102 to prevent the sharp edge of the inner tube from functioning as a trephine.

FIG. 5 illustrates a side view of the punch assembly 400 wherein the deflecting lever 416 has been withdrawn proximally causing increased tension in one of the deflecting wires 412, causing the flexible region 430 to bend 422 out of the longitudinal axis. The punch assembly 400 further comprises the obturator wire 102, the obturator wire grasping tab 108, the stopcock 110, the deflecting lever 416, an axis cylinder 424, the hub 414, the outer tube 406, the inner tube 404, and the bend 422.

Referring to FIG. 5, the deflecting lever 416 has been moved proximally and the axis cylinder 424 causing the top deflecting wire 412 to be placed in tension while the bottom deflecting wire 412 is relaxed. The deflecting wires 412 are affixed at their distal end to the outer tube 406 or the inner tube 404 at a point substantially at or beyond the distal end of the flexible region 420. The distal fixation point (not shown) of the deflecting wires 412 is off-center from the axis of the outer tube 406 or inner tube 404. When uneven tension is created in the opposing deflecting wires 412, the uneven tension on the distal end of the punch 400 causes the bendable region 430 to undergo deflection into a curve or bend 422. Similarly, forward movement of the deflecting lever 416 will place the bottom deflecting wire 412 in tension while the upper deflecting wire 412 will be relaxed, causing the punch 400 to undergo a bend in the opposite direction (downward). The deflecting lever 416 can further comprise a ratchet and lock, a friction lock, a spring-loaded return, or other features to hold position or cause the lever and the bendable region 430 to return to a neutral deflection configuration (substantially straight). The spring nature of the outer tube 406 and the bendable region 430 can advantageously be used to cause a return to neutral once the deflection force is removed from the deflecting lever 416. The stylet or obturator wire 102 can be withdrawn or

extended to expose or protect (respectively) the distal end of the inner tube 404 which can be sharpened or blunted. The obturator wire 102 can further be used as the primary punch, especially if the distal tip of the obturator wire 102 is sharpened. If the obturator wire 102 is used as the primary punch, the proximal end of the inner tube hub is fitted with a Tuohy-Borst or other hemostatic valve to permit the obturator wire 102 to remain in place. In this embodiment, sidearms affixed proximal to the proximal end of the punch, and operably connected to the central lumen, serve to permit pressure monitoring and dye contrast injection without compromising hemostasis or air entry into the punch assembly 400.

FIG. 6 illustrates a side view of an adjustable spacer 600 interconnecting a guide catheter 620 and a punch assembly 100. The spacer 600 further comprises a proximal connector 602, a rotating nut 604, an inner telescoping tube 608, a threaded region 606, a distal locking connector 610, and an outer telescoping tube 614. The guide catheter further comprises a tube 622, a hub 624, and a proximal connector 626. The punch assembly 100 further comprises the stopcock 110, the distal rotating locking connector 612, the inner tube pointer 112, the outer tube pointer 114, and the inner tube hub 116. The spacer 600 can comprise an optional slot 630.

Referring to FIG. 6, the punch assembly 100 is inserted through the central lumen of the adjustable spacer 600. The distal end of the punch assembly 100 is then inserted through the central lumen of the guide catheter 620. The hub 624 of the guide catheter 620 is affixed to the proximal end of the guide catheter tube 622. The distal end of the hub 624 comprises a female Luer lock connection, which is bonded to, or integrally affixed to the hub 624. The hub 624 can further comprise a seal or hemostasis valve such as a Tuohy-Borst fitting. The punch 100 hub 116 is terminated at its distal end by a swivel male Luer lock connector 612. The adjustable spacer 600 comprises an outer telescoping tube 614, shown in partial cutaway view that is terminated at its proximal end with a female Luer lock 602. The proximal end of the outer telescoping tube 614 has a flange that permits rotational attachment of the rotating nut 604, shown in partial cutaway view, so that the rotating nut is constrained in position, longitudinally, relative to the outer telescoping tube 614 but is free to rotate. The inner telescoping tube 608 is affixed at its distal end with a swivel male luer connector 610, or equivalent. The proximal end of the inner telescoping tube 608 is affixed to, or comprises, the integral threaded region 606. The threaded region 606 mates with the internal threads on the rotating nut 604. As the rotating nut 604 is rotated, either manually or by an electromechanical device, it moves forward or backward on the inner telescoping tube 608 and threaded region 606 thus changing the space between the hub 116 of the punch 100 and the proximal end of the hub 624 of the guide catheter 620. The system is preferably set for spacing that pre-sets the amount of needle or stylet travel. In an embodiment, the rotating nut 604 comprises a quick release that allows disengagement of the inner telescoping tube 608 from the outer telescoping tube 614 so that collapse is permitted facilitating the tissue punching procedure of advancing the punch 100 distally relative to the hub 624. The system further comprises hemostatic valves at some, or all, external connections to prevent air leaks into the punch 100. The telescoping tube 608 can be set to disengage from the outer telescoping tube 614 to allow for longitudinal collapse so that the punch 100 can be advanced distally to provide its tissue punching function. In another embodiment, the spacer 600 comprises the slot 630 that permits the spacer to be removed sideways

off the punch **100**. The slot **630** is wide enough to allow the outer tube **106** to fit through the slot **630** so the spacer **600** can be pulled off, or removed from, the punch **100** prior to the punching operation. Thus, the slot **630** can be about 0.048 to 0.060 inches wide and extend the full length of the spacer **600**. With the slot **630**, the spacer **600** comprises a generally "C-shaped" lateral cross-section. The spacer **600** can further comprise a slot closure device (not shown) to prevent inadvertent removal of the punch **100**.

In another embodiment, the threaded region **606** and the rotating nut **604** are replaced by a friction lock on telescoping tubes, a ratchet lock, or other suitable distance locking mechanism. In yet another embodiment, a scale or series of markings (not shown) is incorporated into the adjustable spacer **600** to display the exact distance between the proximal end and the distal end of the spacer **600**. In another embodiment, the proximal end and the distal end of the spacer **600** do not comprise one or both of the female Luer lock **602** or the rotating male Luer lock **610**. In this embodiment, the spacer **600** provides positional spacing but does not affix the punch **100** to the guide catheter **620** so that the two devices move longitudinally as a unit. In another embodiment, the pull wires **412** of FIG. 4, which are strong in tension, but cannot support compression, are replaced by one or more control rods, which are flexible but which have column strength. Thus, deflection can be generated by imparting either tension on the control rod or compression and such tension and compression is capable of deflecting the distal tip of the punch **400** without the need of a separate control rod to impart tension in the other direction. The inner tube hub **116** is terminated at its proximal end by a female Luer, Luer lock, threaded adapter, bayonet mount, or other quick release connector. The quick connect or female Luer can be releasably affixed to a hemostasis valve, other stopcock, pressure transducer system, "Y" or "T" connector for pressure and radiopaque contrast media infusion, or the like.

In another embodiment, a vacuum line can be connected to a port affixed to the proximal end of the punch. The port can be operably connected to a bell, cone, or other structure at the distal end of the punch by way of a lumen, such as the central lumen of the inner tube or an annulus between the intermediate and outer tube, within the punch. By application of a vacuum at the proximal end of the punch, the distal structure can be releasably secured to the atrial septum prior to punching through. In another embodiment, a corkscrew structure projects out the distal end of the punch and is operably connected to a knob or control at the proximal end of the punch by way of a control rod slidably or rotationally free to move within a lumen of the punch. The corkscrew structure can be screwed into tissue to releasably secure the distal end of the punch to the tissue, for example, to enhance stability of the punch prior to, during, or after the punching operation.

Referring to FIG. 1, in another embodiment, the inner tube **104**, the outer tube **106**, or both, are fabricated from shape memory nitinol. In this embodiment, electrical energy can be applied to the pre-bent regions of the inner tube **104**, the outer tube **106**, or both. Upon application of electrical energy, Ohmic or resistive heating occurs, causing temperature of the tubes to increase. The nitinol changes its state from martensitic to austenitic, with the increase in temperature, and can assume a pre-determined configuration or stress state, which is in this case curved. The austenite finish temperature for such a configuration is approximately 40 degrees centigrade or just above body temperature. In yet another embodiment, the austenitic finish temperature can be adjusted to be approximately 28 to 32 degrees centigrade.

The punch **100** can be maintained at room temperature where it is substantially martensitic and non-rigid. Upon exposure to body temperatures when it is inserted into the core lumen of the guide catheter, it will assume its austenitic shape since body temperature is around 37 degrees centigrade. This can cause the punch **100** to curve from substantially straight to substantially curved. In this configuration, only a single tube, either the inner tube **104** or the outer tube **106** is necessary, but both tubes, while potentially beneficial, are not required.

FIG. 7A illustrates a side view, in partial breakaway, of the distal end of an axially elongate outer tube **710**, comprising a lumen **714**, a proximal, uncut portion **712**, a plurality of lateral partial cuts **716**, and a plurality of longitudinal "T" cuts **718**, according to an embodiment.

Referring to FIG. 7A, the outer tube **710** serves as the outer tube of an articulating septal punch such as that illustrated in FIG. 5. The plurality of partial lateral cuts **716** serve to render the region of the outer tube **710** in which the lateral cuts **716** are located more flexible than the proximal region **712**. The plurality of longitudinal "T" cuts, serve to further render the region of the outer tube **710**, in which the "T" cuts **718** reside, more flexible than in tubes where such "T" cuts **718** were not present. The longitudinal "T" cuts **718** are optional but are beneficial in increasing the flexibility of the outer tube **710** in the selected bend region. The partial lateral slots **716** can be spaced apart by about 0.02 to about 1.0 inches with a preferred range of about 0.1 inches to about 0.8 inches and a further preferred range of about 0.15 inches to about 0.5 inches. In an exemplary embodiment, the partial lateral slots **716** are spaced about 0.17 inches apart. The spacing between the partial lateral slots **716** can vary. In some embodiments, for example, the spacing between the partial lateral slots toward the proximal end of the outer tube **710** can be about 0.3 inches while those partial lateral slots **716** nearer the distal end of the outer tube **710** can be spaced about 0.15 inches apart. The spacing can change in a step function, it can change gradually moving from one end of the outer tube **710** to the other, or it can increase and decrease one or more times to generate certain specific flexibility characteristics. Increased spacing increases the minimum radius of curvature achievable by compression of the partial lateral slots **716** while decreased spacing allows for a smaller minimum radius of curvature.

The number of lateral cuts **716** or, optionally, the number of lateral cuts **716** with T-cuts **718** can number between about four and about 50 with a preferred number being between about six and about 25 and a more preferred number of about eight to about fifteen. In the illustrated embodiment, there are 12 partial lateral cuts **716**, each modified with a "T" slot **718**. In other embodiments, the partial lateral cuts **716** can be shaped differently. For example, the partial lateral cuts **716** can be at angles other than 90 degrees to the longitudinal axis, curved, V-shaped, Z-shaped, W-shaped or the like. In other embodiments, the "T" slots **718** can have, for example, further cuts approximately lateral to the longitudinal axis, along any portion of the "T" cut **718**. This construction provides the outer tube with a flexible region at its distal end. The flexible region is a region at the distal end of the outer tube that is significantly more flexible and susceptible to deflection than the remaining proximal region of the outer tube.

The outer tube **710** can have an outer diameter of about 0.020 to about 0.1 inches with a preferred outside diameter of about 0.040 to about 0.060 inches and a more preferred diameter of about 0.045 inches to about 0.055 inches. In the illustrated embodiment, the outside diameter is about 0.048

inches while the inner diameter is about 0.036 inches. The inside diameter of the outer tube **710** can range from about 0.010 inches to about 0.090 inches.

FIG. 7B illustrates an embodiment of a side view, in partial breakaway, of the distal end of an axially elongate inner tube **720**, comprising a lumen **724**, a proximal, uncut portion **722**, a longitudinal slot **726** further comprising an angled lead in **728**, a free side **734**, a pusher or connected side **732**, and a distal tip **730**.

Referring to FIG. 7B, the distal tip **730** interconnects the free side **734** and the pusher side **732**. The distal tip **730** further comprises a tapered distal end that can be beveled or otherwise shaped into a sharp edge such as by circumferentially forming a trephine-like (cylindrical) blade or even a pointed end that is closed or partially closed. The free side **734** and the pusher side **732** are generally integrally formed but can also be affixed to each other by welding, adhesives, fasteners, or the like.

The lead in **728** to the longitudinal slot **726** is beneficially angled to prevent guidewires, stylets, or other catheters, which are inserted through the central lumen **724** from being caught or bumping against an edge. The angled lead in **728** serves a guide to assist with traverse of a stylet, obturator, or guidewire past the lead in **728** and into the distal region of the steerable transeptal needle. The lead in **728** can be angled from between about  $-80$  degrees (the angle can be retrograde) from the longitudinal axis (fully lateral) to about  $+2$  degrees and preferably from about  $+5$  degrees to about  $+20$  degrees with a most preferred angle of about  $+8$  degrees and about  $+15$  degrees. In the illustrated embodiment, the angle of the lead in slot **728** is about 10 degrees from the longitudinal axis. A second feature of the lead in **728** is that it be positioned or located proximally to the most proximal "T" slot **718** in the outer tube **710** when the two tubes **710**, **720** are affixed to each other (see FIG. 9). The lead in **728** is located at least 1-cm proximal to the proximal most "T" slot **718** and preferably at least 2-cm proximal to the proximal most "T" slot **718** so that bending in the distal region does not distort the lead in **728** and cause kinking, misalignment, or pinching of the internal lumen **724**.

The inner or inner tube **720** can have an outside diameter that is slightly smaller than the inside diameter of the outer tube **710** so that the inner tube **720** can be constrained to move longitudinally or axially within the outer tube **710** in a smooth fashion with relatively little force exerted. In the illustrated embodiment, the outside diameter of the inner tube **720** is about 0.033 inches giving about a 0.0015 inch radial clearance between the two tubes **710** and **720**. The inside diameter of the inner tube **720** can range from about 0.002 to about 0.015 inches less than the outside diameter of the inner tube **720**. In the illustrated embodiment, the wall thickness of the inner tube is about 0.006 inches so the inside diameter of the inner tube is about 0.021 inches. The lumen **724** of the inner tube **720** can be sized to slidably accept a stylet or obturator **140** such as illustrated in FIGS. 1 and 2. A typical stylet wire **140** can range in diameter from about 0.01 to about 0.23 inches with a preferred diameter range of about 0.012 to about 0.020 inches. In another embodiment, the outer tube **710** has an outside diameter of about 0.050 inches and an inside diameter of about 0.038 inches. In this embodiment, the inner tube **720** has an outside diameter of about 0.036 inches and an inside diameter of about 0.023 inches. The radial wall clearance between the inner tube **710** and the outer tube **720** is about 0.001 inches and the diametric clearance is about 0.002 inches. The annulus between the two tubes must be substantially smooth, free from burrs, and free from contamination because the two

tubes **710**, **720** beneficially need to translate along their longitudinal axis relative to each other over relatively long axial distances of about 50 to about 150-cm.

The inner tube **720** transmits force along its proximal non-slotted region **722** from the proximal end of the inner tube **720** to the lead in **728** where the force continues to be propagated along the connected side **732** to the distal end **730**. The outer tube **710** transmits force along its proximal non-slotted region **712**. Longitudinal forces applied to the distal, flexible region with the slots **716** cause deformation of the outer tube in an asymmetrical fashion with the side of the outer tube **710** comprising the partial lateral slots **716** forming an outer curve if the slots **716** are expanded and an inside curve if the slots **716** are compressed. Forces to cause bending are preferably exerted such that the partial lateral slots **716** are compressed up to the point where the gap closes, but no further, however forces can also be exerted to expand the slots **716**, however limits on curvature are not in place because the lateral slots **716** can open in an unrestrained fashion except for the material properties of the outer tube **710**.

The disconnected side **734** of the inner tube **720**, separated from the connected side **732** by the longitudinal slot **726** and the lead in **728**, serves to maintain an undistorted tube geometry and provide resistance to deformation while helping to maintain the inner lumen **724** in a round configuration and provide a shoehorn or funnel effect to guide an obturator, guidewire, or stylet **140** therethrough as they are advanced distally. The disconnected side **734**, being separated from the force transmitting member **722** cannot provide any substantial longitudinal load bearing structure, although at its distal end, where it is integral or affixed to the distal end **730**, some tension load carrying capability exists. The inner tube **720** can be considered a split tube and does not carry a load in compression or tension along substantially the entire length of the disconnected side **734**.

The partial lateral slot **716** in the inner, or intermediate, tube **720** and the T-Slot **718** in the outer tube **710**, as well as the longitudinal slot **726** in the inner or inner tube **720**, and the lead in slot **728** can be fabricated by methods such as, but not limited to, electron discharge machining (EDM), wire EDM, photoetching, etching, laser cutting, conventional milling, or the like. In other embodiments, different slot configurations can also be employed, such as curved slots, complex slots, zig-zag slots, or the like. In some embodiments, the partial lateral slot **716** can be configured with a tongue and groove or dovetail design to prevent or minimize lateral movement or torqueing of the outer tube **710** in the flexible region. In some embodiments, the tongue and groove or dovetail (not shown) can be generally centered between two "T" slots, for example. The parts can be ganged and fixture such that, using wire EDM, for example, a plurality of tubes can be cut to reduce manufacturing costs. As many as 20 to 30 tubes, or more, can be fixtured, secured, and etched by the aforementioned methods.

FIG. 8 illustrates a side, cross-sectional view of an embodiment of a hub end **800** of an articulating septal punch. The hub end **800** comprises the outer tube **710**, the inner tube **720**, a hub body **802**, a stopcock petcock **804** further comprising a petcock handle **808** and a petcock through bore **806**, a Luer lock fitting **812**, an arrow pointer **810**, a keyed lumen **834**, a setscrew or pin **820**, a jackscrew body **816** further comprising a plurality of threads **828** and a central lumen **832**, a control knob **814** further comprising a plurality of threads **818**, a central lumen **830**, the protrusion **838**, and a circumferential recess **822**, an outer tube weld **824**, an orientation mark **840**, and an inner tube weld

**826.** The hub body **802** can further comprise a plurality of recesses or complementary structures **836**.

Referring to FIG. 8, the petcock **804** is affixed to the petcock handle **808** by welding, integral fabrication, fasteners, adhesives, or the like. The petcock **804** is retained within a lateral through bore in the hub body **802**, which is in the illustrated embodiment, tapered, using a locking “C” washer, fastener, screw, pin, or the like (not shown). The petcock **804** can be rotated about its longitudinal axis to align the through bore **806** with the axis and central lumen of the hub body **802** or it can be rotated sideways to shut off and seal the lumen against the flow of fluids. The Luer lock **812** can be affixed to, or integrally fabricated with, the hub body **802**. The knob **814** is retained within the hub body **802** by the setscrew of pin **820** which prevents axial movement but permits rotational movement as constrained by the setscrew, projection, or pin **820** riding within the circumferential recess **822** which is integrally formed or affixed to the knob **814**. The jackscrew body **816** is capable of axial movement within the hub body **802** but is restrained from rotation about the long axis by flats or features on the exterior of the jackscrew body **816** which are constrained by flats or features in the keyed lumen **834**. The knob **814** comprises threads **828** on its internal lumen which engage with external threads **818** on the jackscrew body **816**. Rotation of the knob **814** thus causes the jackscrew body **816** to move axially proximally or distally with mechanical advantage. Rotation of the knob **814** can be forced using manual action or using a motor or other mechanism (not shown). The outer tube **710** is affixed to the jackscrew body **816** by the outer tube weld **824**. The inner tube **720** (which can also be called the inner tube) is affixed to the hub body **802** by the inner tube weld **826**. The central lumen **724** of the inner tube **720** is operably connected to a central lumen of the hub body **802**, the petcock through bore **806**, and the lumen of the Luer fitting **812**.

The knob **814** can comprise markings **840** to permit the user to visualize its rotary or circumferential position with respect to the hub body **802**. These markings **840** can comprise structures such as, but not limited to, printed alphanumeric characters (not shown), a plurality of geometric shapes such as dots, squares, or the like, or the markings can comprise raised or depressed (embossed) characters of similar configuration as described for the printed markings. In an embodiment, the knob **814** can comprise a number on each of the facets so the facets can be numbered from one to 6, in the illustrated embodiment. The knob markings **840** can further comprise raised structures, as illustrated, which can further be enhanced with contrasting colors for easy visualization.

The knob **814** can further comprise one or more complementary structures affixed or integral thereto, such as a plurality of protrusions **838** that fit into detents **836** affixed or integral to the proximal end of the hub body **802**. Such protrusions extending into detents in the hub body **802** can provide a ratcheting or clicking sound as well as providing resistance to inadvertent movement of the knob **814** once it is rotated to the correct location. The knob **814**, in some embodiments, can be biased toward the hub body **802** to ensure that complementary structures such as the protrusions and detents come into correct contact. In other embodiments, the knob **814** can comprise a ratchet system to further control its rotary movement with respect to the hub body **802**. In other embodiments, the knob **814** can comprise one or more detents (not shown) while the hub body **802** can comprise one or more complementary protrusions (not shown). It is beneficial that the knob **814** be moved only

when required by the user and not by accident or not when it is required to maintain its rotary position and, by consequence, the curvature at the distal end of the tubing. The number of ratchet locations, or low energy positions or set points, can range from about 2 per 360 degree rotation to about 20 with a preferred number of ratchet locations ranging from about 4 to about 12.

The hub body **802** can be fabricated from biocompatible metals such as, but not limited to, stainless steel, titanium, nickel coated brass, cobalt nickel alloy, and the like, although it could also be fabricated from polymeric materials in a less expensive format. The knob **814** can be fabricated from the same metals as the hub body **802** but it can beneficially be fabricated from biocompatible polymers such as, but not limited to, polyamide, polyimide, polyvinyl chloride (PVC), acrylonitrile butadiene styrene (ABS), acetyl polymers, polycarbonate, polysulfone, PEEK, Hytrel®, Pebax®, and the like. The petcock **804** and petcock handle **808** can be fabricated from the same materials as the knob **814**, or it can be different materials. The jackscrew body **816** can be fabricated from the same materials as the hub body **802**, or from different materials, but must be able to be strongly affixed to the outer tube **710**.

FIG. 9 illustrates a side view, in partial breakaway, of an embodiment of a distal end **900** of an articulating trans-septal punch with any stylets removed. The distal end **900** comprises the outer tube **710** further comprising the lateral partial slits **716** and the intermediate (or inner) tubing **720** further comprising the longitudinal slit **726** and the distal tip **730**. A weld **902** affixes the distal end of the outer tube **710** to the connected side **732** of the inner tube. The distal end **900** can further comprise one or more separate radiopaque markers **904**.

Referring to FIG. 9, outer tube **710** and the inner tube **720** are rotated about the longitudinal axis such that the connected side **732** of the inner tube **720** is generally aligned with, and affixed or welded **902** to, the outer tube **710** on the side comprising the partial lateral slits **716**. The width of the partial lateral slits **716**, the T-slots **718**, and the longitudinal slot **726** can range from about 0.001 to about 0.050 inches with a preferred range of about 0.005 to about 0.020 inches. In the illustrated embodiment, the slits **716**, **718**, and **726** are about 0.010 inches. The width of the partial lateral slits **716** on the outer tube **710** can be used, in compression to provide at least some limit to how much the outer tube **710** can bend in compression along the side comprising the partial lateral slits **716**. Note that the inner tube **720** extends beyond the distal end of the outer tube **710**. In the illustrated embodiment, the inner tube **720** extends about 10 mm to about 20 mm beyond the distal end of the outer tube **710**. This construction provides for reduced device complexity, increased reliability of operation, and reduced manufacturing costs relative to other steerable devices. The system also provides for high stiffness when the distal end **900** is straight, as illustrated, curved as in FIG. 11, or curved, bent, deflected, steered, or otherwise deformed in any configuration between straight and maximally curved. The articulating trans-septal punch is necessarily stiff, has high column strength, and has significant resistance to bending from external sources because it needs to force an incision through tissue at the end of a very long, 2 to 4 foot length, of very small diameter punch tubing. Thus, the all-metal tubing punch can translate forces from its proximal end to its distal end that a polymeric catheter could not come close to equaling. Catheters carrying such a punch would be less effective for the specific purpose of transseptal puncturing than would the articulating trans-septal needle.

The distal end **900** of the articulating trans-septal punch is generally fabricated from metals with sufficient radiopacity or radio-denseness that they are clearly visible under fluoroscopic or X-ray imaging. However, if this is not the case, additional radiopaque markers **904** can be affixed to the outer tube **710**, the inner tube **720**, or both. These radiopaque markers can comprise materials such as, but not limited to, tantalum, gold, platinum, platinum iridium, barium or bismuth compounds, or the like.

Close tolerances between the internal diameter of the outer tube **710** and the outside diameter of the inner tube **720**, ranging from a radial gap of between about 0.0005 inches to about 0.008 inches, depending on diameter cause the two tubes **710** and **720** to work together to remain substantially round in cross-section and not be ovalized, bent, kinked, or otherwise deformed. This is especially important in the flexible distal region comprising the partial lateral cuts **716** on the outer tube **710** and the longitudinal slot **726** in the inner or inner tube **720**. The two tubes **710** and **720** can be fabricated from the same materials or the materials can be different for each tube **710**, **720**. Materials suitable for tube fabrication include, but are not limited to, stainless steel, nitinol, cobalt nickel alloy, titanium, and the like. Certain very stiff polymers may also be suitable for fabricating the tubes **710**, **720** including, but not limited to, polyester, polyimide, polyamide, polyether ether ketone (PEEK), and the like. The relationship between the inner tube **720**, the outer tube **710**, and the slots **716**, **718**, **726**, **728** serve to allow flexibility and shaping in high modulus materials such as those listed above, which are not normally suitable for flexibility. The internal and external surface finishes on these tubes **710**, **720** are preferably polished or very smooth to reduce sliding friction between the two tubes **710**, **720** because of their very small cross-sections and their relatively long lengths. Lubricants such as, but not limited to, silicone oil, hydrophilic hydrogels, hydrophilic polyurethane materials, PFA, FEP, or polytetrafluoroethylene (PTFE) coatings can be applied to the inner diameter of the outer tube **710**, the outer diameter of the inner tube **720**, or both, to decrease sliding friction to facilitate longitudinal relative travel between the two tubes which is necessary for articulating the flexible, slotted region near the distal end **900** of the articulating transeptal sheath. The exterior surface of the outer tube **710** can be covered with a polymeric layer, either substantially elastomeric or not, which can cover the slots **716**, **718**, etc. and present a smoother exterior surface to the environment. The exterior surface can be affixed or configured to slip or slide over the exterior of the outer tube **710**.

The weld **902** affixes the outer tube **710** to the intermediate or inner tube **720** such that they cannot move relative to each other along the longitudinal axis at that point. However, since the two tubes **710**, **720** are affixed to each other on the side of the outer tube **710** containing the partial lateral slots or gaps **716**, compression or expansion of those gaps **716** can be accomplished by moving the weld **902** by relative movement of the inner tube **720** and the outer tube **710**. The weld transmits the force being carried by the connected side **732** of the inner or inner tube **720** to the slotted side of the outer tube **710**. Note that the terms inner tube **720** and inner tube **720** are used interchangeably, by definition. The inner tube **720** becomes an inner tube **720** if another tube or catheter is passed through its internal lumen **724**.

In other embodiments, since the inner or inner tube **720** is split **726** lengthwise in the flexible region, a portion, or the entirety, of the distal end of the inner tube **720** can be affixed,

adhered, welded, fastened, or otherwise attached to the outer tube **710** and functionality can be retained. The distal end **730** of the inner tube **720** can, in some embodiments be retained so as to create a cylindrical distal region **730** in the inner tube **720** and this entire cylindrical distal region **730**, or a portion thereof that does not project distally of the distal end of the outer tube **710** can be welded to the outer tube **710** around a portion, or the entirety of the circumference of the outer tube **710**. If only a portion of the inner tube **720** is welded to the outer tube **710**, then the weld is beneficially located, approximately centered, on the side of the outer tube **710** comprising the partial lateral slots **716**. The cylindrical distal region **730** is a beneficial construction, rather than completely cutting the inner tube **720** away on one side, since the distal region **730** projects distally of the distal end of the outer tube **710** to form the tip of the punch further comprising a sharpened tip **1102**, **1302** configured to punch through myocardial tissue (refer to FIGS. **11** and **13**).

In some embodiments, one of the welds, all of the welds, or a portion of the welds can be completed using techniques such as, but not limited to, TIG welding, laser welding, silver soldering, fasteners, adhesives, plasma welding, resistance welding, interlocking members, or a combination thereof. Laser welding is beneficial because it is highly focused and can be located with high accuracy. These welds include the weld **902** at the distal end that connects the inner tube **720** and the outer tube **710** as well as the welds at the proximal end connecting the inner tube **720** to the hub and the outer tube **710** to the traveler of the jack-screw **816**.

FIG. **10** illustrates an oblique external view of an embodiment of the proximal end **800** of the steerable trans-septal needle comprising the outer tube **710**, the knob **814**, the hub body **802**, the arrow pointer **810** further comprising the pointed end **1004**, a stopcock body **1006**, the petcock **804**, the petcock handle **808**, and the Luer fitting **812** further comprising a locking flange **1002**.

Referring to FIG. **10**, the pointed end **1004** can be integrally formed with the arrow pointer **810**, or it can be affixed thereto. The arrow pointer **810** can be integrally formed with the hub body **802**, or it can be affixed thereto using fasteners, welds, adhesives, brazing, soldering, or the like. The stopcock body **1006** can be integrally formed with the hub body **802** or it can be affixed thereto using fasteners, welding, soldering, brazing, adhesives, threads, bayonet mounts, or the like. Referring to FIGS. **8** and **10**, the lumen of the Luer fitting **812** is operably connected to the through bore of the petcock **804** if the petcock **804** is aligned therewith (as illustrated), or the petcock **804** can be rotated about an axis to misalign the through bore of the petcock **804** with the Luer fitting **812** and prevent fluid flow or passage of solid material therethrough. The knob **814** can be round, shaped as a lever, it can comprise knurls, facets (as illustrated), or it can comprise a plurality of projections which facilitate grabbing and rotation by the user. Circumferential motion of the knob **814** about its longitudinal axis is preferably and beneficially smooth but with sufficient friction to maintain its position in any desired configuration.

FIG. **11** illustrates an embodiment of the distal end **900** of the articulating trans-septal needle in a curved configuration. The distal end **900** comprises the outer tube **710**, the inner tube **720**, the outer tube lumen **714**, the distal end of the proximal region of outer tube **712**, the distal end **730** of the inner tube **720** further comprising the sharpened distal tip **1102**, the plurality of outer tube longitudinal cuts or slots **718**, and the plurality of outer tube partial lateral cuts **716**.

Referring to FIG. **11**, the outer tube partial lateral cuts **716** represent spaces that close up when the side of the tube in

which the lateral cuts **716** are located is placed in compression. Such compression is generated by pushing the outer tube **710** distally relative to the inner tube **720**. When the partial lateral cuts **716** gaps close, further compression is much more difficult because the outer tube **710** stiffens substantially when no further gap exists for compression. The composite structure, with the inner tube **720** nested concentrically inside the outer tube **710** is relatively stiff and resistant to kinking no matter what amount of curvature is being generated. Such stiffness is essential when using the articulating trans-septal needle to bend or steer another catheter such as a Mullins introducer, or other guide catheter.

Preferred radius of curvatures for the distal end can range from about 1 inch to about 6 inches, with a preferred range of about 2 inches to about 4 inches and a more preferred range of about 2.5 to about 3.5 inches for the purpose of puncturing the atrial septum. Even smaller radius of curvatures would be appropriate in, for example, the cerebrovasculature, the arteries of the heart, and the like. The radius of curvature need not be constant. In some embodiments, the proximal end of the flexible region can have the partial lateral cuts spaced more widely than those at the distal end of the flexible region, causing the distal end to bend into a tighter radius than, the proximal end of the flexible region. In other embodiments, the distal region can be less flexible than the proximal end of the flexible region.

The partial lateral cuts **716**, and the "T"-slots in the outer tube **710** are beneficially treated using etching, electropolishing, passivation, sanding, deburring, machining, or other process to round the external edges of the partial lateral cuts **716**. Thus, the edges are blunted or rounded so they are not sharp such as to cause the articulating trans-septal needle to dig, skive, or shave material from the inside of a polymer guide catheter since that is a primary benefit of using the articulating trans-septal needle rather than a pre-curved, non-articulating, trans-septal needle or other punch that, when advanced distally through a polymeric sheath, can scrape or skive material from the inner diameter of the sheath or introducer.

The distal end **1102** can be sharp in some embodiments but it can also be somewhat or completely blunted. In the case of partially or completely blunted distal construction, the distal end can be operably connected to a source of electrical or radiofrequency (RF) energy and puncture holes can be created using the electrical or RF energy. The energy is carried by the inner tube **720**, which is preferably electrically insulated from the outer tube **710**, from the hub **900** into which electrical or RF energy can be applied to the distal tip **1102**.

FIG. **12A** illustrates a top view of another embodiment of an outer tube **1200** in the region of the distal, flexible section, wherein the outer tube **1200** comprises a plurality of partial lateral cuts or slots **1206** further comprising a dovetail **1202**. The dovetail **1202** creates a groove **1202** and further comprises a peg or projection **1204** that rides or is circumferentially constrained within the groove **1202** as long as the outer tube **1200** is neutrally forced, or forced in compression on the side of the partial lateral cuts or slots **1206**. The projection **1204** riding within the dovetail groove **1202** provides for torque resistance and torsional rigidity in the area of the dovetail **1202**.

FIG. **12B** illustrates a side view of the outer tube **1200** in the region of the distal, flexible section, wherein the outer tube **1200** comprises the partial lateral slots **1206**, the dovetail **1202** further comprising the projection **1204**, and the "T" slots **718**. The T-slots **718** are optional or they can be configured differently.

The punch can be used to create holes in various structures in the body. It is primarily configured to serve as an articulating or variable deflection Brockenbrough needle. However, the steerable punch can be used for applications such as transluminal vessel anastomosis, biopsy retrieval, or creation of holes in hollow organs or lumen walls. The punch can be used in the cardiovascular system, the pulmonary system, the gastrointestinal system, or any other system comprising tubular lumens, where minimally invasive access is beneficial. The punch can be configured to be coring or non-coring in operation, depending on the shape of the distal end and whether an obturator or the circular hollow end of the punch is used to perform the punching operation. In the coring configuration, a plug of tissue is removed using, for example, a cylindrical cutting blade at the distal end while in the non-coring configuration, substantially no tissue is removed from the patient. The punch facilitates completion of transseptal procedures, simplifies routing of the catheters, minimizes the chance of embolic debris being dislodged into the patient, and improves the ability of the cardiologist to orient the punch for completion of the procedure. The punch of the present invention is integral and steerable. It is configured to be used with other catheters that may or may not be steerable, but the punch disclosed herein does not require external steerable catheters or catheters with steerability to be steerable as it is steerable or articulating on its own. The punch is capable of bending and unbending a practically unlimited number of times. The punch is especially useful with catheters that are not steerable since the punch comprises its own steering system.

The punch can be removed from the lumen of a catheter after it completes perforation of the hollow organ or vessel wall, through which it is placed, so as to maximize the size of said lumen and allow for advancement of devices such as diagnostic mapping catheters, ablation catheters, catheters to place atrial appendage closure devices, mitral valve repair devices, mitral valve replacement devices, annuloplasty rings, and the like. Without removal of the punch, the lumen is compromised and the capacity of the sheath to introduce catheters is reduced, given a certain outside diameter. Minimizing the outside diameter of the sheath is important in preventing a damaged fossa Ovalis. This device is intended for use with catheters and is not intended for use as integral to a catheter. This device steers itself and can steer a catheter but is not a replacement for a steerable catheter. For instance, an introduction sheath or guide catheter can be steered and bendable but if the trans-septal punch is not steerable and is pre-bent, advancement of the pre-bent trans-septal punch through the sheath or guide catheter and its obturator, steerable or not, will cause the sharp distal end of the trans-septal punch to shave or skive off debris or material from the inside diameter of the obturator of the sheath or guide catheter or the catheters themselves. This shaving or skiving can occur even when the trans-septal punch is protected by a central obturator, stylet, inner tube, or guidewire. Use of a steerable obturator does not help the situation because a pre-bent, trans-septal punch, advanced through a straight, steerable obturator will still shave off or skive material from the inside diameter of the obturator.

The steering mechanism disclosed herein in FIGS. **7A** & **7B** through-FIG. **11** can be used to steer other types of catheters, guide catheters, introducers, sheaths, guidewires, or even obturators that are placed within the aforementioned devices, with high degree of control over long lengths up to 250 cm or more while requiring less wall thickness and thus allowing for larger internal lumens than steerable devices of the prior art with the same outside diameter. Typical sheaths

can have internal lumens with capacities of, for example, 6-Fr to 12-Fr and still maintain very thin walls of around 1-Fr. While smaller catheters or guide catheters with lumens in the range of about 2-Fr to 5-Fr can have even smaller wall thicknesses, depending on the materials used to construct the walls of the sheath. Some sheath constructions can comprise composite materials such as an inner tube fabricated from metal and an outer tube fabricated from metal with a polymeric exterior coating. The inner tube can further be coated with an interior liner of, for example PTFE, or other fluoropolymers (PFA, FEP), Parylene, Pebax®, Hytrel®, polyimide, polyamide, PET, or the like, to create certain reduced frictional properties, electrically insulating properties, or both. These coatings or liners can range in thickness from about 0.0001 to about 0.005 inches, with a preferred thickness range of about 0.0005 to 0.002 inches. Electrical insulating properties are important if electrically conductive catheters are inserted through one or more lumens of a guide catheter or introducer whose mechanical properties are derived from high strength materials such as, in certain embodiments, conductive metal. Electrical insulating properties are also important should the device itself be used for electrical purposes such as, but not limited to, RF Ablation, RF hole puncturing, RF coagulation, and the like.

The steering mechanism disclosed herein, comprising two or more nested axially elongate cylindrical tubes moving relative to each other only along the longitudinal axis, can provide a high degree of precision, repeatability, force, column strength, torsional control, and the like, in a configuration with extremely thin walls and large inside diameter (ID) to outside diameter (OD) ratio. One of the tubes comprises partial lateral cuts or complex lateral gaps and the other tube comprising a split running substantially the length of the flexible region. The disconnected side of the slit tube can be removed so that only a partially formed, connected side remains. However, in preferred embodiments, the disconnected side, which is actually retained at the distal end, is not removed but serves to fill space within the lumen of the outer tube **710** to prevent kinking, improve column strength, prevent lumen collapse and provide for guiding of central stylets or catheters. Prior art devices require greater wall thickness, which reduces the size of the internal lumen relative to a given outside diameter, or they do not have the same degree of precise movement at the distal tip under control from the proximal end of the device.

FIG. 13 illustrates a side view of the distal end **900** of an articulating transeptal punch advanced through a central lumen **1312** of a dilator or obturator **1310** of a guide catheter **1314**. The articulating transeptal punch distal end **900** comprises the outer tube **710**, comprising the plurality of partial lateral cuts **716**, and the inner tube **720**, comprising a sharpened distal tip **1302**. The sharpened distal tip **1302** comprises a bevel **1304**, one or more facets **1308**, a point **1318**, and a rounded or blunted outside edge **1306**. The obturator **1300** further comprises the central lumen **1312**. The guide catheter **1314** further comprises a central lumen **1316**.

Referring to FIG. 13, the guide catheter **1314** and its obturator **1310** are generally curved near the distal end. When the distal end **900** is advanced distally through the lumen **1312** of the obturator **1310**, scraping of the inner wall of the obturator **1310** is prevented by inclusion of a rounded edge **1306** of the distal end **1302** toward the outside of the curvature. The distal sharp end **1302** comprises a bevel **1304** to create a sharpened tissue punch with a point **1318**. The facets **1308** are optional but can be provided in numbers ranging from one to about 10. The bevel **1304** can be

generated at a single angle, or with a complex curvature. In some embodiments, the bevel **1304** can be generated at an angle of about 20 to about 80 degrees from lateral to the axis of the tube with a preferred range of about 30 to about 60 degrees from lateral, and a most preferred range of about 40 to about 50 degrees. The point **1318** can be a point in three dimensions or in two dimensions, such as the point **1318** illustrated herein.

FIG. 14 illustrates the distal end **900** of an articulating transeptal punch further comprising a stylet **1400**. The stylet comprises the core wire **1402**, the proximal lock **1404** (not shown), a collapsing shield **1408**, and the rounded distal tip **1406**.

Referring to FIGS. 13 and 14, the stylet **1400** is slidably and removably inserted through the central lumen of the inner tube **720** to assist with blunting the sharpened distal end. Stylets sufficiently small to fit through these central lumens of the inner tube **720** are generally quite small, having a diameter of about 0.012 to 0.015 inches and are necessarily very weak. They are subject to bending and kinking and cannot hide a sufficient amount of the distal pointed end **1302** to prevent damage to the inside of a polymeric guide catheter **1314** or its obturator **1310**. Because the inner tube **720** has a very thick wall relative to its overall diameter, a wire inserted through the central lumen of the inner tube **720** cannot protect or shield the distal end **1302** adequately. Thus, a regular stylet **1400** is only partially useful in preventing skiving material from the inside of the guide catheter **1314** or obturator **1310** unless it includes the collapsing shield **1408**. A radially collapsing feature **1408** of the obturator **1400** can be beneficial in protecting the distal end with more completeness than a non-collapsing version. The collapsing feature **1408** is collapsed radially, laterally, or diametrically by withdrawing the obturator **1400** inside the inner tube **720** and it expands on its own using self-expansion under spring bias, shape memory recovery, or the like. The obturator **1400** can be fabricated from materials such as, but not limited to, stainless steel, nitinol, cobalt nickel alloy, titanium, and the like using methods such as cold rolling or tempering to achieve substantial spring conditions. In the illustrated embodiment, the collapsing shield feature **1408** is created by means of a split tube of spring stainless steel, comprising a plurality of slots or openings **1410** which are biased outward to create a bulge when unrestrained. The slotted tube shield **1408** is integral or affixed to the core wire **1402**. The amount of outward bulge of the shield **1408** is not large but is sufficient to substantially equal or exceed the wall thickness of the inner tube **720**.

In some embodiments, the outer tube **710** can be modified to adjust stiffness. It can be preferential to increase the resistance to bending moving distally to proximally on the outer tube **710**. This increase in bending resistance contravenes the tendency of the outer tube to bend more severely at the proximal end of the flexible region than in the distal region. It is possible to configure the bending so that the bend radius is approximately constant or such that a greater curvature (smaller radius of bending) is generated moving toward the distal end of the bendable region. The partial lateral slots **716** can be cut with reduced depth more proximally to increase the resistance to bending imparted by the outer tube **710**. The partial lateral slots **716** can be cut more narrowly in the more proximal regions to reduce the distance the slot **716** can close. The T-slots **718** can be reduced in length or removed in the more proximal regions of the flexible region of the outer tube **710**. Elastomeric bumpers or fillers can be added to some of the partial lateral slots **716**

to reduce the amount the partial lateral slots **716** can compress. Once the partial lateral slots **716**, associated with the T-slots **718** have closed under bending of the outer tube **710**, further bending is resisted and is substantially arrested. By tailoring the width and spacing of the partial lateral slots **716**, a specific final curvature can be tailored for a given catheter.

FIG. **15A** illustrates the outer tube **710** comprising the lumen **714**, the proximal tube wall **712**, the plurality of partial lateral slots **716**, the plurality of T-slots **718**, a short partial lateral slot **1502**, a slightly longer partial lateral slot **1504**, and a standard length lateral slot **716** but with a shortened T-slot **1506**.

Referring to FIG. **15A**, the most proximal partial lateral slot **1502** penetrates less than the standard partial lateral slots **716**. The second (moving distally) partial lateral slot **1504** is slightly longer than slot **1502** and therefore is more flexible in that region and requires less force to generate bending. The third partial lateral slot comprises the shortened T-slot **1506** which reduces the ability of the tubing to bend given a constant bending force.

FIG. **15B** illustrates the inner tube **720** comprising the lumen **724**, the proximal region **722**, the connected side **732**, the distal end **730**, the sharpened tip **1302**, and a beveled lead-in **1510** at the proximal end of the distal end **730**.

Since, during use of the steerable transseptal needle, the needle is advanced distally through an already placed introducer, sheath, or guide catheter, it is beneficial that the straight steerable transseptal needle be capable of advancing through any curvatures in the already placed introducer, sheath, or guide catheter. Thus, in certain embodiments, the bevel is oriented such that the pointed point of the sharpened tip **1302** is oriented toward the direction of bending. In this way, the steerable transseptal needle, when in its straight configuration, can be pushed against into the curved region of the introducer, sheath, or guide catheter and not have the sharp point dig into the wall of the introducer, sheath, or guide catheter. The side of the sharpened tip **1302** away from the sharp point can further be rounded somewhat to make it even more atraumatic and smooth so it can skate or sled along the curvature of the introducer, sheath, or guide catheter without digging out any material from the wall of the introducer, sheath, or guide catheter.

Referring to FIG. **15B**, the proximal end of the disconnected region can be moved distally to increase the stiffness of the inner tube **720** in a specific region, generally the most proximal part of this distal, flexible region.

In certain preferred embodiments, it is beneficial that the inner tube **720** can sustain compression to generate bending of the outer tube **710** at the distal end back to straight after being curved and even to bend beyond straight in the other (or opposite) direction. In order to sustain compression, it is beneficial that the disconnected side **734** be separated from the connected side **732** at or near substantially the center or midpoint of the tubing. Depending on the width of the slot **726** separating the disconnected side **734** from the connected side **732**, the location of the slot can be offset from the midpoint but this is dependent on the wall thickness of the inner tube **720** and the angle of the slotting. In a preferred embodiment, interference exists between the disconnected side **734** and the connected side **732** such that the disconnected side and force transmitting member cannot move substantially inward, a situation that would have negative effects of obstructing the lumen, restricting fluid flow there-through, trapping stylets or other catheters that need to move

longitudinally therein, or buckling sufficiently to prevent application of longitudinal compression forces on the connected side **732**.

FIG. **16A** illustrates a lateral cross-sectional view an inner tube **720** nested inside an outer tube **710** and separated from the outer tube **720** by a radial gap **1602** in the flexible region of an articulating septal punch wherein the inner tube **720** is separated by a split or gap **726** into two approximately or substantially equal parts, a connected side **732** and a disconnected side **734**, approximately (or substantially) at the midline or centerline of the cross-section.

FIG. **16B** illustrates a lateral cross-sectional view an inner tube **720** nested inside an outer tube **710** and separated from the outer tube **720** by a radial gap **1602** in the flexible region of an articulating septal punch wherein the inner tube **720** is separated by a split or gap **726** into two substantially unequal parts, a connected side **732** and a disconnected side **734**, substantially offset from the midline or centerline of the cross-section.

Referring to FIGS. **16A** and **16B**, the disconnected side **734** is retained in close proximity to the outer tube **710** by its stiffness and its inability to deform such that the edges of the disconnected side **734** can pass beyond the edges of the connected side **732** and thus the two sides **732** and **734** are retained radially displaced from centerline. If the gap **726** were too large or either side **732**, **734** were small enough to fit within the edges of the other side, then displacement of one side toward the centerline and confounding of the off-center orientation of the connected side **732** or **734** would occur leading to buckling of the connected side **732** in compression and inability to straighten out a bent transseptal needle. Another problem might be loss of torqueability and predictability of the direction of bending. Both embodiments shown in FIGS. **16A** and **16B** maintain circumferential and radial orientation of the inner tube connected side **732** relative to the disconnected side **734** and promote high precision deflection of the distal tip.

In preferred embodiments, the radial gap **1602** is minimized and is retained between about 0.0005 to 0.002 inches when the needle is about 0.050 in outside diameter. Furthermore, the split or gap **726** should be as minimal as possible and in preferred embodiments can range from about 0.002 inches to about 0.015 inches with a gap of about 0.004 to 0.010 inches being most preferable.

The embodiments presented in FIGS. **7** through **16** describe a system that does not use pull wires or push rods. There are no side lumens required in either the outer tube or the inner tube. Such side lumens, as found in certain prior art catheters, require extensive cross-sectional area be used to surround the side lumens and take away from the potential area for the central lumen since the outside extent of the catheter is limited. The use of control rods or pull wires requires such as those in certain prior art catheters, retaining these structures along one side of the outer tube so it does not obstruct the lumen, which is needed for stylets, fluid injection, radiopaque dye injection, and the like. Side lumens or channels are necessary to retain a pull wire or control rod in the correct location so as to provide correct off center forces to bend the distal end. The side lumens are also necessary to keep the control rod or pull wires out of the central lumen which needs to remain open and substantially circular. The system disclosed herein, however, retains a high degree of column strength, maximum torqueability, the largest possible central lumen, and a very strong control and steering function or capability. Furthermore, the side lumens or channels are necessary to maintain spatial (rotational orientation) for the articulating distal end of the device. Without

the side lumens or channels permitting axial slidability but generating radial retention, the pull wires or pushrods would be free to migrate around within the central lumen of the device and could bend the device in an unwanted direction. Long catheters or needles with relatively small cross-sectional areas are highly subject to torque and rotational misalignment and some method must be employed to retain the correct circumferential location of the articulating apparatus.

Furthermore, a pull-wire as used in prior art devices is incapable of generating compression against the distal end of the device so a pull-wire could not, under compression, move or articulate the distal end of the device. The pull-wire, under tension, can move or articulate the distal end and would require some sort of counterforce such as an opposing pull-wire, shape memory metal, or spring return biasing to move the distal end in the reverse direction. A pull-wire with a diameter of about 0.010 inches (0.0000785 square inches) would sustain tension loads of about 500,000 PSI, to generate a pull force of 40 pounds or 250,000 PSI to generate a pull force of 20 pounds, beyond the capability of most known metals or polymers. Forces exceeding 20 pounds can be necessary to cause bending and stiffening of a Brockenbrough needle to generate the appropriate column strength and bending resistance such that the fossa Ovalis can be penetrated by the needle. An unconstrained push-rod or control rod of almost any diameter will buckle under these types of loads and be unable to generate oppositional forces under compression to articulate the distal end in the reverse direction sufficiently to make the device clinically acceptable.

However, a tubular or cylindrical central control device can maintain its structure in compression, maintain circumferential location within the outer cylindrical, axially elongate tube, maintain precise control, maintain sufficient tensile strength to exert forces up to and exceeding 40 pounds, and maintain a central lumen larger than any other type of steerable device. The resistance to buckling occurs even when the inner tube is slotted longitudinally because the inner tube is constrained within the outer tube using very tight tolerances that will not let the inner tube bend out of its straight orientation, even under compression.

FIG. 17A illustrates a lateral cross-sectional view of the shaft 1700 of a steerable needle or punch. The shaft comprises an outer tube 710 further comprising a lumen 1710, a plurality of control rods 1702, a plurality of control rod spaces 1706, and a resultant central lumen 1712.

Referring to FIG. 17A, the control rods 1702 are slidably disposed within the lumen 1710 outer tube 710, as well as relative to each other. The illustrated embodiment shows three control rods 1702, which can also be termed push rods, pull rods, or linkages, all of which include the mechanical properties to be able to exert compression as well as tension, and optionally torque, on an object being controlled. In some embodiments, one or more of the plurality of control rods 1702 can serve as a control rod retainer and not be affixed to any specific item. The control rods 1702 are affixed at their distal end to the outer tube, distal to a region of increased flexibility or bendability relative to a more proximal region of the outer tube 710. The plurality of control rods 1702, are retained away from the resultant central lumen 1712 and substantially against the inner diameter of the outer tube 710 by the narrow spacing 1706. The three control rods 1702 are configured to provide for steering, deflection, or articulation of the distal end of the steerable needle or punch about multiple axes. Each control rod 1702 can be moved independently, or in concert, along the lon-

gitudinal axis under the influence of different actuators, controllers, hydraulic actuators, electrical actuators, pneumatic actuators, levers, knobs, jackscrews, or the like.

The outer tube 710, the control rods 1702, or both, can be fabricated from materials such as, but not limited to, polyimide, polyamide, polyester, polyurethane, silicone, PEEK, PTFE, PFA, FEP, stainless steel, nitinol, titanium, cobalt nickel alloys, and the like.

FIG. 17B illustrates a lateral cross-sectional view of another embodiment of the shaft 1712 of a steerable needle or punch. The shaft 1712 comprises an outer tube 710 further comprising a lumen 1710, a plurality of control rods 1704, a plurality of control rod spaces 1708, and a resultant central lumen 1714. The shaft 1712 further comprises an intermediate or inner tube 1716 which can serve as a keeper and as a fluid-tight barrier, or liner, to prevent the migration of fluids, gas or liquid, across so as to maintain the central lumen leak-free and fluid impermeable central lumen 1718.

Referring to FIG. 17B, the inner tube 1716 can be fabricated from materials such as, but not limited to, polyimide, polyamide, polyester, polyurethane, silicone, PEEK, PTFE, PFA, FEP, stainless steel, nitinol, titanium, cobalt nickel alloys, and the like. The wall thickness of the inner tube can range from about 0.0005 inches to about 0.010 inches, with a preferred range of about 0.0007 to about 0.005 inches. The inner tube 1716 can be affixed to the hub (not shown) at the proximal end and to the distal end of the outer tube 710, either directly or through an intermediary structure which could include a bonding ring or at least one of the control rods 1702.

FIG. 18A illustrates a lateral cross-sectional view of another embodiment of the shaft 1800 of a steerable needle or punch. The shaft 1800 comprises the outer tube 710 further comprising a lumen 1810, a control rod 1804, a control rod retainer 1806, guide, or keeper, a plurality of control rod spaces 1808, and a resultant central lumen 1814. The shaft 1800 further comprises an intermediate or inner tube 1716 which can serve as a keeper and as a fluid-tight barrier, or liner, to prevent the migration of fluids, gas or liquid, across so as to maintain a central lumen leak-free and fluid impermeable central lumen 1818. A stylet 1812 is slidably disposed within the fluid impermeable central lumen 1818.

Referring to FIG. 18A, the control rod 1804 is slidably disposed within the lumen 1810 and retained against or near the internal wall of the outer tube 710 by the control rod retainer 1806. The plurality of control rod spaces 1808 between the control rod 1804 and the control rod retainer 1806 are intentionally kept as small as possible without generating excessive friction that would hinder longitudinal relative movement between the control rod 1804 and the control rod retainer 1806, as well as between the control rod 1804 and the outer tube 710. In the illustrated embodiment, the plurality of control rod spaces 1806 are about 0.002 inches wide while the radial distance between the outer wall of the control rod and the inner wall of the inner tube is about 0.001 inches. These spaces could be increased up to, but not beyond, the point where the retaining function of the control rod retainer 1806 is defeated and the control rod 1804 can move laterally into the center of the lumen 1814. The outer tube 710 is shown with a 0.050 inch OD and a wall thickness of about 0.006 inches with a range of about 0.001 to 0.020 inches. The control rod 1804 is illustrated with a wall thickness of about 0.008 inches but can range from about 0.001 to about 0.020 inches.

FIG. 18B illustrates a lateral cross-sectional view of another embodiment of a shaft 1820 of a steerable needle or

punch. The shaft **1820** comprises the outer tube **710** further comprising the lumen **1810**, two control rods **1822**, a control rod retainer **1806**, guide, or keeper, a plurality of control rod spaces **1824**, and a resultant central lumen **1814**. A stylet **1812** is slidably disposed within the central lumen **1814**.

Referring to FIG. **18B**, the control rod retainer **1806** can be affixed at the distal end of the outer tube **710**, it can be affixed at a hub (not shown), or it can be affixed to the outer tube at a point intermediate the hub and a bendable region in the outer tube **710**. In a preferred embodiment, the control rod retainer **1806** is affixed to the outer tube at one axial location only. In another embodiment the control rod retainer **1806** is not affixed to the outer tube or the inner tube, but rather rides loosely within the outer tube **710** held in place by the control rods **1822**. This structure applies to all the control rods and control rod retainers described within this specification.

The two control rods **1822** are affixed at their proximal end to a hub (not shown) or a control mechanism within a hub (not shown) allowing the control rods **1822** to be independently moved longitudinally, or axially, relative to the outer tube **710**, under manual or assisted control. Such assisted control includes, but is not limited to, rotational electric motors, pneumatic actuators, stepping motors, linear electric motors, hydraulic actuators, and the like and may further be controlled by computers, robotic devices, or other automated control systems. The two control rods **1822** can, in other embodiments, be one or both affixed directly to the hub, or through an intermediary member, such that any relative motion between the control rods and the outer tube is brought about by moving the outer tube by an actuator while the control rods, one or both, remain affixed to the hub, directly or through an intermediary member such as another tube, anchor, fastener, or the like. Affixation can be performed using methods and devices such as, but not limited to, welds, laser welds, silver solder, fasteners, adhesives, mechanical interlock, ultrasonic welds, or the like.

At the distal end, the control rods **1822** can be affixed directly to the outer tube **710** distal to a region of enhanced flexibility or through an intermediary such as a separate tube, linkage, control rod, fastener, or the like. The control rods **1822** can be affixed at a same point or at different locations along the circumference or longitudinal axis of the outer tube **710**.

FIG. **18C** illustrates a side view of a control rod and keeper system **1850** comprising a c-cross-sectional shaped control rod **1804** and a c-cross-sectional shaped control rod keeper, guide, or retainer **1806**. This configuration is shown in lateral cross-section in FIG. **18A**. The control rod **1804** can extend or run substantially the entire working length of the steerable needle between a hub (not shown) and a region distal to any deflectable or steerable regions of the outer tube **710** (refer to FIGS. **18A** and **18B**). The control rod **1804** can also be configured to retain its C-shape only within the approximate region of a bendable or articulating region of the outer tube **710**. In other areas, proximal and distal to the bendable region, the control rod **1804** can be affixed or integral to a pusher rod, which can be solid or hollow, or other tubular structure. The control rod **1804** is affixed, or integral to a distal tubing extension **1854**, which can be optionally terminated with a sharp point, as shown, or with a rounded blunt end, with a tapered dilator, or the like. The distal tubing extension **1854** steps up, in the illustrated example, to a larger diameter at the point **1860**. The distal tubing extension **1854** can be integral, or affixed to the

control rod **1804** or the control rod guide **1806** by a weld, adhesive bond, mechanical fastener, solder joint, brazing joint, or the like.

Referring to FIG. **18C**, the c-shaped control rod guide or retainer **1806** can be completely disconnected from the control rod **1804**, or it can be affixed at a point distal to the flexible region, at a point proximal to the flexible region, but not both proximal and distal. In other embodiments, the control rod retainer **1806** can be affixed to the outer tube **710** but not to the control rod **1804**. The control rod retainer **1806** serves the function of forcing the control rod **1804** laterally off-center to maintain off-center within the outer tube **710** and for filling the lumen of the outer tube **710** to prevent collapse of the lumen and kinking during articulation or bending.

FIG. **19A** illustrates a lateral cross-sectional view of another embodiment of a shaft **1900** of a steerable needle or punch. The shaft **1900** comprises the outer tube **710** further comprising the lumen **1910**, one or more "V" shaped control rod **1902**, a resultant central lumen **1910**. A stylet **1812** can be slidably disposed within the central lumen **1910**.

Referring to FIG. **19A**, the V-shaped control rod **1902** can be slidably disposed within the lumen **1910** of the outer tube **710** such that it can be axially displaced without substantial resistance, yet it is still constrained against substantial lateral movement due to the space restrictions within the lumen **1910**.

FIG. **19B** illustrates a lateral cross-sectional view of another embodiment of a shaft **1920** of a steerable needle or punch. The shaft **1920** comprises the outer tube **710** further comprising the lumen **1910**, one or more "U" shaped control rod **1922**, a resultant central lumen **1910**. The stylet **1812** can be slidably disposed within the central lumen **1910**.

Referring to FIG. **19B**, the U-shaped control rod **1922** can be slidably disposed within the lumen **1910** of the outer tube **710** such that it can be axially displaced without substantial resistance, yet it is still constrained against substantial lateral movement due to the space restrictions within the lumen **1910**.

Referring to all the control rods disclosed herein, these control rods can extend the entire length of the device from the hub or handle to a region distal to any flexible regions or regions of enhanced bendability in the outer tube. The control rods can also be affixed or integral to rods, tubing, or other structures extending part way through the device but not traversing the flexible regions or regions of enhanced bendability. The control rods can be affixed to the hub or handle by way of an anchor, weld, adhesive, mechanical interlock, actuator, or the like. The control rods can further comprise hinges or areas of substantially increased flexibility proximate one or both of the ends, proximal and distal.

FIG. **20A** illustrates a lateral cross-sectional view of another embodiment of a shaft **2000** of a steerable needle or punch. The shaft **2000** comprises the outer tube **710** further comprising the lumen **1910**, one or more hollow, round control rods **2002**, the control rods further comprising a resultant central lumen **2004**. This arrangement does not leave room for a large diameter, round stylet but it does provide for a substantial lumen for fluid flow **1910** within the outer tube **710**.

FIG. **20B** illustrates a lateral cross-sectional view of another embodiment of a shaft **2020** of a steerable needle or punch. The shaft **2020** comprises the outer tube **710** further comprising the lumen **1910**, one or more hollow, round control rods **2002**, and an off-center but full size stylet **1812**. This arrangement does provide for a lumen for fluid flow **1910** within the outer tube **710** and the stylet **1812** further

provides the function of the control rod retainer, when the stylet **1812** is in place within the lumen **1910**.

FIG. **21A** illustrates a lateral cross-sectional view of another embodiment of a shaft **2100** of a steerable needle or punch. The shaft **2100** comprises the outer tube **710** further comprising the lumen **1910**, a rectangular control rod **2102**, the control rod **2102** further comprising a central lumen **2104**. A round stylet can be retained within the lumen **2104** and it does provide for a substantial lumen **1910** for fluid flow within the outer tube **710**.

Referring to FIG. **21A**, the distal end of the control rod **2102** can be affixed to the outer tube **710** on one side or another thus generating some offset forces to bend the outer tube **710**.

FIG. **21B** illustrates a lateral cross-sectional view of another embodiment of a shaft **2120** of a steerable needle or punch. The shaft **2200** comprises the outer tube **710** further comprising the lumen **1910**, and an I-Beam shaped control rod **2122**. A round stylet cannot be retained within the lumen **1910** but it does provide for a substantial lumen **1910** for fluid flow within the outer tube **710**, even greater than that for the embodiment shown in FIG. **21A**. Note that the edges of the control rods **2122** and **2102** in FIGS. **21A** and **21B** are rounded to provide a smoother fit within the lumen **1910**, but this rounding, or even part of it, is optional.

FIG. **22A** illustrates a lateral cross-sectional view of another embodiment of a shaft **2200** of a steerable needle or punch. The shaft **2200** comprises the outer tube **710** further comprising the lumen **1910**, and a round, solid control rod **2202**. A round stylet (shown in FIG. **22B**) can be retained within the lumen **1910** by moving the control rod **2202** off-center and it does provide for a substantial lumen **1910** for fluid flow within the outer tube **710** but little control over the radial or circumferential position of the control rod within the outer tube **710** is provided.

FIG. **22B** illustrates a lateral cross-sectional view of another embodiment of a shaft **2220** of a steerable needle or punch. The shaft **2220** comprises the outer tube **710** further comprising the lumen **1910**, and a round, hollow control rod **2222** further comprising a lumen **2204**. The stylet **1812** is retained within the lumen **2204** of the hollow control rod **2222**.

FIG. **23A** illustrates a lateral cross-sectional view of another embodiment of a shaft **2300** of a steerable needle or punch. The shaft **2300** comprises the outer tube **710** further comprising the lumen **1910**, and a round, hollow control rod retainer **2302** further comprising a central lumen **2304** and a plurality of retainer grooves **2306**, and a plurality of control rods or pull wires **2308**. A round stylet (shown in FIG. **22B**) can be retained within the lumen **2304** but is left out of this illustration.

Referring to FIG. **23A**, the control rods or pull wires **2308** are illustrated as solid but can comprise structures such as, but not limited to, stranded, tubular, circularly braided, flat braided, continuous tubular, slotted tubular, or the like. The grooves **2306**, which can be termed channels, slots, or the like, are beneficially cut or formed into the exterior of the control rod retainer **2302**. In other embodiments, these grooves **2306** could be replaced by one or more off-center lumens (not shown) within the cross-section of the control rod retainer **2302**. The control rod retainer **2302** can be affixed at one or more points within the outer tube **710** or it can be free floating. The central lumen **2304** is capable of accepting another wire or control rod, a stylet, or fluid.

FIG. **23B** illustrates a lateral cross-sectional view of another embodiment of a shaft **2320** of a steerable needle or punch. The shaft **2320** comprises the outer tube **710** further

comprising the lumen **1910**, an arcuate or curved, c-shaped control rod retainer **2322** and an arcuate or c-shaped cross-section control rod **2328**. The control rod **2328** and the control rod retainer **2322** are separated by a plurality of gaps or spaces **2324**. A round stylet (not shown here but shown in FIG. **22B**) can be retained within the remaining lumen **2326**.

Referring to FIG. **23B**, the spaces **2324** between the control rod retainer **2322** and the control rod **2328** do not radiate from the center in a radial direction but rather at an angle from the radial direction. The spaces **2324** between the control rod retainer **2322** and the control rod **2328** are drawn at about 0.002 inches spacing but that spacing could be between about 0.0005 and 0.015 inches with a preferable spacing of between about 0.001 and 0.008 inches.

FIG. **24A** illustrates a lateral cross-sectional view of another embodiment of a shaft **2400** of a steerable needle or punch. The shaft **2400** comprises the outer tube **710** further comprising the lumen **1910**, an arcuate or curved control rod **2402** which subtends approximately 270 degrees of circumference on the inside diameter of the outer tube **710**. A round stylet **1812** is illustrated as slidably, and removably, retained within the remaining lumen **1910** which is defined by the curvature in the center of the arcuate control rod **2402**.

Referring to FIG. **24A**, the arcuate control rod **2402** is retained against the side wall of the outer tube **710** by its shape, being greater than 180 degrees in circumference. Because the arcuate control rod **2402** is not a full 360 degree control rod, it will have somewhat increased bending and decreased resistance, relative to a fully circular control rod, to lateral forces imposed thereupon.

FIG. **24B** illustrates a lateral cross-sectional view of another embodiment of a shaft **2420** of a steerable needle or punch. The shaft **2420** comprises the outer tube **710** further comprising the lumen **1910**, an arcuate or curved control rod **2428** which subtends approximately 180 degrees of circumference on the inside diameter of the outer tube **710**, along with an arcuate control rod retainer **2422** which further subtends approximately 180 degrees within the outer tube **710**. A plurality of slits, or slots, **2426** separate the control rod **2428** and the control rod retainer **2422**.

The control rod retainer **2422** of FIG. **24B** is smaller in wall thickness than that of the control rod **2428** to permit greater fluid flow rates therein and still keep the control rod **2428** against the inside wall of the outer tube **710** and offset from the centerline.

FIG. **25A** illustrates a lateral cross-sectional view of another embodiment of a shaft **2500** of a steerable needle or punch. The shaft **2500** comprises the outer tube **710** further comprising the lumen **1910**, an arcuate or curved control rod **2502** which subtends approximately 180 degrees of circumference on the inside diameter of the outer tube **710**, along with an arcuate control rod retainer **2504** which further subtends approximately 180 degrees within the outer tube **710**. A plurality of slits, or slots, **2506** separate the control rod **2502** and the control rod retainer **2504**. This configuration is similar to that shown in FIG. **18A** except that the control rod **2502** and the control rod retainer **2504** subtend a greater arc than the device of FIG. **18A** and thus, the gaps **2506** are much smaller, in this case about 0.002 inches and leaving very little room for lateral displacement of the control rod **2502**. The outer tube **710**, as shown, is an 18 gauge tube with an outside diameter of about 0.050 inches and an inside diameter of about 0.038 inches. This diameter can change to suit the occasion but the concept of tight tolerances between the inner and outer structures is important in retaining alignment and off-center positioning.

37

FIG. 25B illustrates a lateral cross-sectional view of another embodiment of a shaft 2520 of a steerable needle or punch. The shaft 2520 comprises the outer tube 710 further comprising the lumen 1910, an arcuate or curved control rod 2522 which subtends approximately 180 degrees of circumference on the inside diameter of the outer tube 710, along with an arcuate control rod retainer 2524 which further subtends approximately 180 degrees within the outer tube 710. A plurality of slits, or slots, 2526 separate the control rod 2522 and the control rod retainer 2524. This configuration is similar to that shown in FIG. 25A except that the control rod 2522 and the control rod retainer 2524 subtend a significantly reduced arc than the device of FIG. 25A and thus, the gaps 2526 are much larger, in this case about 0.009 inches and leaving much more room for lateral displacement of the control rod 2522. As in FIG. 25A, the outside arc of the control rod 2522 and the control rod retainer 2524 is a close fit with the inside diameter of the outer tube 710, having only a gap of about 0.001 inches. Since the materials used in all the elements can be metallic, friction from longitudinal relative translation is low and is not a major factor relative to the forces needed to bend the structure.

FIG. 25C illustrates a lateral cross-sectional view of another embodiment of a shaft 2540 of a steerable needle or punch. The shaft 2540 comprises the outer tube 710 further comprising the lumen 1910, an arcuate or curved control rod 2542 which subtends approximately 180 degrees of circumference on the inside diameter of the outer tube 710, along with an arcuate control rod retainer 2544 which further subtends approximately 180 degrees within the outer tube 710. A plurality of slits, or slots, 2546 separate the control rod 2542 and the control rod retainer 2544. This configuration is similar to that shown in FIG. 25B, with approximately the same slot width 2546, except that the control rod 2542 and the control rod retainer 2544 comprise a significantly reduced outside diameter than the device of FIG. 25B, and thus, the gap 2548 between the control rod 2542 and the inside diameter of the outer tube 710, as well as that of the control rod retainer and the inside diameter of the outer tube 710 are much larger and leave much more room for lateral displacement of the control rod 2542 and the retainer 2544.

FIG. 26A illustrates a lateral cross-sectional view of another embodiment of a shaft 2600 of a steerable needle or punch. The shaft 2600 comprises the outer tube 710 further comprising the lumen 1910. The shaft 2600 further comprises a plurality of solid control rods or wires 2602, an intermediate or inner tube 2606, and a stylet 1812. The plurality of control rods or wires 2602 ride within the annulus 2610 comprised between the outside of the intermediate or inner tube 2606 and the inside of the outer tube 710.

FIG. 26B illustrates a lateral cross-sectional view of another embodiment of a shaft 2620 of a steerable needle or punch. The shaft 2620 comprises the outer tube 710 further comprising the lumen 1910. The shaft 2620 further comprises a plurality of hollow control rods or wires 2622, an intermediate or inner tube 2606, and a stylet 1812. The plurality of control rods or wires 2622 ride within the annulus 2610 comprised between the outside of the intermediate or inner tube 2606 and the inside of the outer tube 710. The hollow control rods or wires 2622 can be tubular in configuration and either solid wall or fenestrated, woven, braided, or the like.

Referring to FIGS. 26A and 26B, the inner tube 1606 restrains the control wires or rods 1606, 2622 radially off-center but does not provide much resistance against circumferential misalignment.

38

FIG. 27A illustrates a lateral cross-sectional view of another embodiment of a shaft 2700 of a steerable needle or punch. The shaft 2700 comprises the outer tube 710 further comprising the lumen 1910 and a solid, full diameter control rod 2702 that is slidably disposed or constrained within the lumen 1910 with adequate wall clearance such that minimal friction is encountered but maximum bracing against kinking of the outer tube 710 is provided.

FIG. 27B illustrates a lateral cross-sectional view of another embodiment of a shaft 2720 of a steerable needle or punch. The shaft 2720 comprises the outer tube 710 further comprising the lumen 1910 and a plurality of solid, partial diameter control rods 2722 that are slidably disposed within the lumen 1910 with adequate wall clearance, and comprise gaps or space 2726 from each other, such that minimal friction is encountered but maximum bracing against kinking of the outer tube 710 is provided. The plurality of control rods 2722 can be hollow or solid. They can be fabricated from tubes, and filling the center, or from a round, solid bar. The central gap 2726 can be fabricated by slotting a tube or bar or by forming the two parts separately.

FIG. 28A illustrates a lateral (side) view of a distal, deflectable region 2800 of a steerable needle or punch. The distal deflectable region 2800 comprises the outer tube 2802, with a first plurality of radially directed, partial cuts or gaps 2804 oriented in a first direction, and a second plurality of radially directed partial cuts or gaps 2806 oriented in a second direction. The gaps 2802 and 2804 are formed in the wall such that not all cut 2802 cuts are grouped together but are, in at least one case, interleaved with the cuts 2804. The distal deflectable region 2800 further comprises a first control rod 1802, a second control rod 1804, and a control rod retainer or keeper 1806, each separated by a plurality of slots 1810. The deflectable region 2800 further comprises the first weld 2814 and the second weld 2812.

Referring to FIG. 28A, the two control rods 1802 and 1804 are able to separately apply off-center forces on the outer tube 2802 and, due to the selective ability of the outer tube to bend in the first and second directions, cause the outer tube to flex or articulate in these two directions. The stability of the control rod 1802 allows the second control rod 1804 to flex the tube without closing or opening the gaps 2804 but instead closing or opening the gaps 2806. The same condition is true for the control rod 1804 stabilizing longitudinal movement of the outer tube against opening or closing of the gaps 2806 in a specific direction so that the control rod 1802 can flex the outer tube in the direction of the gaps 2804.

The control rods 1802 and 1804 can be separately affixed to the outer tube 2802 distal to the articulating region or they can be affixed together and to the outer tube 2802 distal to the articulating region. The control rods can be affixed together, to the outer tube, or to an intermediary structure such as another tube using methods such as, but not limited to, welding, soldering, fasteners, mechanical interlock, adhesive bonding, and the like. In the illustrated embodiment, the first control rod 1802 is affixed to the outer tube by the first weld 2814 and the second control rod 1804 is affixed to the outer tube by the second weld 2812. These welds 2812, 2814 can preferably be laser welds or silver soldered joints although the other listed methods can also be used.

FIG. 28B illustrates a cross-section 2820 of the tubing 2800 in the distal articulating region as viewed in the direction shown. The cross-section 2820 comprises the outer tube 2802, the central lumen 1808, the first control rod 1802, the second control rod 1804, the control rod retainer 1806, and the plurality of gaps 1810.

FIG. 29A illustrates a lateral (side) view of a distal, bi-directionally deflectable region 2900 of a steerable needle or punch. The distal bi-directionally deflectable region 2900 comprises a first outer tube region 2906, with a first plurality of radially directed, partial cuts or gaps 2916 oriented in a first direction, a second outer tube region 2904 comprising a second plurality of radially directed partial cuts or gaps 2914 oriented in a second direction. The cuts or fenestrations 2914 and 2816 are formed in the wall such that all cuts or gaps 2914 or 2916 are grouped together in their respective outer tube regions 2904 and 2906. The distal deflectable region 2900 further comprises a first control rod 1802, a second control rod 1804, and a control rod retainer or keeper 1806, each separated by a plurality of slots 1810. The deflectable region 2900 further comprises the first weld 2908 and the second weld 2910, which are located at different axial locations along the tubing. The distal end of the outer tube 2918, located axially distal to the deflectable region, is terminated distally by a sharp point 2920 and affixed to one or more of the control rods 1802, 1804, the control retainer 1806, the distal-most outer tube 2926, or one or more of these by a fixation point, arc, or ring 2922, which can be a weld, adhesive bond, solder joint, mechanical fastener, integral fabrication, intermediary structure or the like.

Referring to FIG. 29A, the two control rods 1802 and 1804, affixed to the outer tube at different locations immediately distal to their respective articulating regions 2904, 2906 by welds 2910 and 2908, are able to separately apply off-center forces on the outer tube regions 2904 and 2906 and cause the outer tube to flex or articulate in these two directions within their specific locations 2906, 2904. The stability of the control rod 1802, in both compression and tension, allows the second control rod 1804 to flex the 2906 tube without closing or opening the gaps 2914 but instead closing or opening the gaps 2916. The same condition is true for the control rod 1804 stabilizing longitudinal movement of the outer tube against opening or closing of the gaps 2916 in a specific direction so that the control rod 1802 can flex the outer tube in the direction of the gaps 2914.

The control rods 1802 and 1804 are separately affixed to the outer tube distal to their respective articulating. The control rods can be affixed to the outer tube, or to an intermediary structure such as another tube using methods such as, but not limited to, welding, soldering, fasteners, mechanical interlock, adhesive bonding, and the like. In the illustrated embodiment, the first control rod 1802 is affixed to the outer tube by the first weld 2910 and the second control rod 1804 is affixed to the outer tube by the second weld 2908. These welds 2908, 2910 can preferably be laser welds or silver soldered joints although the other listed methods can also be used.

FIG. 28B illustrates a cross-section 2950 of the tubing region 2904 in the distal articulating region as viewed in the direction shown. The cross-section 2950 comprises the outer tube 2904, the central lumen 1808, the first control rod 1802, the second control rod 1804, the control rod retainer 1806, and the plurality of gaps 1810.

FIG. 30A illustrates a lateral (side) view of a distal, bi-directionally deflectable region 3000 of a steerable needle or punch. The distal bi-directionally deflectable region 3000 comprises an outer tube 3006, with a plurality of radially directed, partial cuts or gaps 3008 oriented in a first direction, and further comprising a distal end 3010. The distal region 3000 further comprises a hollow tubular control rod 3002, a central lumen 3004, a distal weld 3016, a tubing extension 3012 optionally terminated by a sharp point 3014,

and a hinge region 3020 created, in this embodiment, by a cut 3018 in the control rod 3002.

Referring to FIG. 30A, the cuts or fenestrations 3008 are formed in the wall such that all cuts or gaps extend and transect approximately 50% of the diameter of the tube. This transection or cut can range from about 10% to about 90% of the diameter with a preferred range of about 30% to about 70% of the diameter. The transaction can be a simple cut with a rounded end, as illustrated, it can have substantially no rounding, or it can comprise T-slots at the end to facilitate bending depending on the strength of the material and resistance to bending. The transection can comprise a width of about 0.001 to about 0.020 inches with a preferred range of about 0.005 to about 0.015 inches and a most preferred range of about 0.007 to about 0.012 inches. The control rod 3002 can be affixed to the distal-most outer tube 3010, distal to any flexibility enhancing features such as the transections 3008, by a fixation point, arc, or ring 3016, which can be a weld, adhesive bond, solder joint, mechanical fastener, integral fabrication, intermediary structure or the like.

This configuration retains the internal lumen as mostly fluid-tight and leak free, except in the region of the hinge cutout 3018 in the control rod 3002. To prevent leakage through the slots 3008 from the slot 3018, a pressure shroud 3018 is affixed around the exterior of the outer tube. This pressure shroud can comprise, for example, a shrink wrapped or bonded tube of polyester, polyurethane, PTFE, FEP, PFA, or the like. The wall thickness of the pressure shroud 3018 can range from about 0.00025 inches to about 0.010 inches with a preferred range of about 0.0005 to about 0.005 inches and a most preferred range of about 0.0007 to about 0.002 inches.

The central lumen 3004 is capable of serving as a leak-free channel for infusion and withdrawal of fluids, both liquid and gas, and can serve as a pressure monitoring lumen, for example, without concern for migration of materials out of, or into, the sides of the device.

The hinge 3020, generated by cutting a notch 3018 in the control rod 3002 is optional. The hinge 3020 could also be fabricated using more standard hinge construction comprising a pin and loops or by the inclusion of materials of elastomeric nature to permit flexing.

FIG. 30B illustrates a cross-section 3050 of the tubing region 3006 in the distal articulating region as viewed in the direction shown. The cross-section 3050 comprises the outer tube 3006, the central lumen 3004, the hollow control rod 3002, and the gap 3522 between the control rod 3002 and the outer tube 3006.

Referring to FIG. 30B, the gap 3522 needs to be enough to prevent binding of the control rod 3002 against the outer tube 3006 during bending. The gap 3006 can be sized radially between about 0.001 and 0.025 inches with a preferred gap of about 0.005 to about 0.020 inches, with a most preferred gap of about 0.010 to 0.015 inches.

FIG. 31A illustrates a side view, in partial breakaway, of the distal end of a steerable transseptal needle 3100 comprising an outer tube 3112, an inner tube 3106, further comprising a lumen 3108 and a blunted distal end 3110, a stylet 3102 further comprising a sharp, pointed, distal end 3104, which is shown retracted inside the lumen 3108, a control rod 3114, and a keeper or stay 3116.

Referring to FIG. 31A, the sharp tip 3104 can be formed integrally to the stylet 3102. The sharp tip 3104 can be conical and be sharpened to angles ranging from about 10 degrees to about 60 degrees from the longitudinal axis, per side. The blunted distal end 3110 of the inner tube 3106 can comprise a full round approximately equal to the wall

thickness, a taper, a chamfer, or the like. The inner tube **3106** is small in diameter and is difficult to make completely non-sharp but it is blunted to the extent possible. The control rod **3114** is illustrated and extends within the bendable region of the steerable transseptal needle. Sufficient space can exist around the stylet shaft **3102** and within the lumen **3108** to permit fluids to be injected and withdrawn or pressure measurements to be taken. In another embodiment, the stylet wire shaft **3102** can comprise one or more longitudinal slots (not shown) to increase fluid flow area therethrough. The stylet wire or shaft **3102** can also have a star shaped cross-section, a C-shaped cross-section, or the like. The sharp tip **3104** is retracted sufficiently inside the blunted end **3110** that there is no risk of unwanted tissue or guide catheter shaft puncture or damage while the steerable transseptal needle is being advanced or positioned. The piercing stylet in this embodiment is capable of punching through tissue more sharply than the native distal end of the apparatus.

FIG. **31B** illustrates a side view of the distal end of the steerable transseptal needle **3100** with the stylet **3102** advanced beyond the blunted distal end of the inner tube **3110** to expose the sharp tip **3104**. The steerable transseptal needle comprises the outer tube **3112**, the inner tube **3106** with the blunted distal end **3110**, the stylet **3102**, shown advanced, further comprising the sharp, pointed, distal end **3104**, the control rod **3114**, and the keeper or stay **3116**.

Referring to FIG. **31B**, the sharp tip **3104** is advanced sufficiently to provide for a clean tissue puncture and so that the pierced tissue can ride over the stylet shaft **3102**, over the blunted distal end **3110**, and onto the outside of the inner tube **3106**. Projection of the inner tube **3106** beyond the outer tube **3112** is traditionally about 1.5 cm. This distal projection distance of the inner tube **3106** can be maintained so that the sharp tip **3104** projects beyond the 1.5 cm or the inner tube **3106** projection can be reduced so that the sharp tip **3104** is positioned at approximately 1.5 cm (or less) from the outer tube **3112**, when the stylet is fully advanced.

FIG. **32A** illustrates a side view, in partial breakaway, of the distal end of a steerable transseptal needle **3200** comprising the outer tube **3112**, the inner tube, **3106** further comprising the lumen **3108** and the blunted distal end **3110**, the stylet **3102** further comprising a neck down **3210** to a smaller diameter more proximal stylet shaft **3208**, the sharp, pointed, distal end **3104**, which is shown retracted inside the lumen **3108**, the control rod **3114**, the keeper or stay **3116**, a radiopaque marker **3202** further comprising a radiopaque marker lumen **3204**, and a radiopaque marker retainer **3206**.

Referring to FIG. **32A**, the radiopaque marker **3202** can comprise materials such as, but not limited to, tantalum, platinum, gold, platinum iridium, or the like. The radiopaque marker **3202** is preferably affixed within the lumen **3108** but can, in other embodiments, be affixed to the exterior of the inner tube **3106**. The radiopaque marker **3202** can be affixed to the wall of the inner tube **3106**, as is, or the inner tube **3106** wall can be machined to create an increased diameter on the ID or a decreased diameter on the OD to accept the radiopaque marker **3202**. The radiopaque marker **3202** can be affixed to the inner tube **3106** by welding, adhesive bonding, swaging, a combination thereof, or the like. In an embodiment, the inner tube **3106** can be formed down to a smaller diameter after the radiopaque marker is installed to prevent the radiopaque marker from ever being dislodged.

FIG. **32B** illustrates a side, partial breakaway view of the distal end of the steerable transseptal needle **3200** with the stylet **3102** advanced to expose the sharp end **3104** distal to the distal end **3210** of the inner tube **3202**. The steerable

transseptal needle **3200** comprises the outer tube **3112**, the inner tube **3106**, further comprising the lumen **3108** and the blunted distal end **3110**, the stylet **3102**, further comprising the smaller diameter more proximal stylet shaft **3208**, the sharp, pointed, distal end **3104**, which is shown advanced and exposed beyond the end of the inner tube **3106**, the inner tube lumen **3108**, the control rod **3114**, the keeper or stay **3116**, the radiopaque marker **3202** further comprising the radiopaque marker lumen **3204**, and the radiopaque marker retainer **3206**.

Referring to FIG. **32B**, the lumen **3204** of the RO marker **3202** is sufficiently large that the stylet wire **3102** can slidably project therethrough with no appreciable drag or binding. The RO marker lumen **3204** should be at least approximately 0.002 inches larger in diameter than the OD of the stylet shaft **3102**.

FIG. **33A** illustrates a side view, in partial breakaway, of the distal end of a steerable transseptal needle **3300** comprising all the elements of the steerable transseptal needle **3200** of FIGS. **32A** and **32B**, but wherein the sharp pointed end **3104** of the stylet **3102** is replaced by a beveled, sharp end **3302**. The beveled end **3302** can be angled at about 10 degrees to about 60 degrees from the longitudinal axis of the stylet wire **3102**. The beveled end **3302** can further comprise one or more facets, not shown.

FIG. **34A** illustrates a side view of a stylet hub **3400** comprising the proximal length of stylet wire **3102**, the hub body **3402**, further comprising a hub lumen **3416**, a male Luer taper **3414**, and a male Luer lock feature **3412**, a spring housing **3404**, a push cap **3406**, a wire retaining tube **3408**, a spring **3410**, an O-Ring **3418**, and an O-ring retainer **3420**. The stylet hub **3400** is shown with the push cap **3406** and its spring container retracted, as biased by the spring **3410**.

Referring to FIG. **34A**, the hub body **3402**, the spring housing **3404**, the cap **3406**, and the O-ring retainer **3420** can comprise plastic such as, but not limited to, polycarbonate, polysulfone, PEEK, PVC, ABS, or the like. The parts can be assembled using adhesive bonding, solvent bonding, ultrasonic welding, interference snap fits, or the like. The spring housing **3404** slides axially over the OD of the hub body **3402** and these two parts are not bonded together. The cap **3406** is affixed to the wire holding tube **3408** using adhesive bonding, a mechanical interference, or the like. The stylet wire **3102** can be affixed to the holding tube **3408** using laser welds, silver solder, crimping, mechanical fasteners, or the like. The O-ring **3418** prevents fluid leakage through the lumen **3416** into the interior of the spring housing **3404** where it could escape and cause patient hemorrhage. Air ingress through the lumen **3416** could also lead to an air embolism and thus needs to be prevented by this O-ring. The spring **3410** can be fabricated from materials such as, but not limited to, stainless steel, nitinol, titanium, cobalt nickel alloy, or the like. In the illustrated embodiment, the spring **3410** is an open coil, when relaxed, but could also be a leaf spring or other spring structure. The spring **3410** biases the hub **3400** to keep the stylet **3102** fully retracted except when activation is required. In the illustrated embodiment, the spring **3410** is fabricated from stainless steel and comprises an OD of 0.25 inches and a wire diameter of about 0.01 to 0.03 inches, with a preferred wire diameter of about 0.015 to 0.014 inches.

FIG. **34B** illustrates a side view of the stylet hub **3400** with the spring compressed and the push cap **3406** and its spring housing **3404** fully advanced to compress the spring **3410**. The stylet hub **3400** comprises the proximal length of stylet wire **3102**, the hub body **3402**, further comprising the hub lumen **3416**, the male Luer taper **3414**, and a male Luer

lock feature 3412, the spring housing 3404, the push cap 3406, the wire retaining tube 3408, and the spring 3410. The stylet wire 3102 is now advanced distally due to distal relative motion of the push cap 3406.

FIG. 35A illustrates a side view of a stylet hub 3500 comprising the hub body 3402 further comprising the Luer lock feature 3412, the male Luer taper 3414, an enlarged diameter grip 3504 around the male Luer lock feature 3412, the spring housing 3404, the push cap 3406, and a safety clip 3502.

Referring to FIG. 35A, the safety clip 3502 resides within the depression created by the spring housing 3404 and the enlargement 3504. The safety clip 3502 comprises a grip region and a c-shaped section that removably snaps around the barrel of the hub body 3402. Thus, the C-shape comprise sufficient opening to permit easy attachment and release of the C-clip 3502 by grasping the grip region or handle. The safety clip 3502 prevents the user from advancing the spring housing 3404 and cap 3406 distally. Once the safety clip is removed, the spring housing 3404 and cap 3406 can move distally, under spring compression, to force the stylet shaft 3102 distally. The safety can comprise other structures that permit such a safety feature. Such safety features can comprise integral switches, control knobs, mechanical interlocks, or the like.

FIG. 35B illustrates an oblique view of the stylet hub 3500, comprising the spring housing 3404, the Male Luer lock feature 3412, the male Luer taper 3414, and the removable safety clip 3502. The threads forming the male Luer lock feature 3412 can be clearly seen. These threads interlock with threads on the flange of a female Luer lock connector to form a bayonet mount or screw mount to securely maintain attachment. When fully secured, the hub 3500 or 3400 are positioned precisely with relation to the hub 3500 or 3400 on the steerable transseptal needle (FIG. 36), thus providing for precise locating and function of the stylet tip protrusion distance.

FIG. 36A illustrates an exterior side view of a steerable transseptal needle 3600 with its distal end curved 90 degrees. The steerable transseptal needle comprises the stylet 3102 (not shown because it is retracted), the stylet hub 3500, further comprising the stylet hub button 3404 and cap 3406, the safety clip 3502, the bendable region of the needle 900, the steerable transseptal needle hub 800, and the blunted distal end 3110.

Note that the stylet hub 3500 can be released and removed from the hub 800 of the steerable transseptal needle 3600. Although a Luer lock is shown as the preferred attachment, any type of quick connect can be used such as, but not limited to, mechanical fastener, bayonet mount, screw mount, or the like.

FIG. 36B illustrates the steerable transseptal needle of FIG. 36A with the safety clip 3502 removed but the activation button 3404, 3406 on the stylet hub 3500 has not been advanced or depressed.

FIG. 36C illustrates the steerable transseptal needle of FIG. 36B with the activation button 3404, 3406 on the stylet hub 3500 having been depressed and causing the stylet 3102, and its sharp tip 3104, to be exposed distally beyond the end 3110 of the inner tube.

In other embodiments, the stylet hub can comprise a quick release feature for the spring. In these embodiments, when a control button is pushed, an intermediate structure is engaged and forces the stylet shaft 3102 distally until a certain point is reached, wherein the intermediate structure is disengaged and the spring forces the stylet shaft 3102 proximally. This disengagement can result from mechanical

action that spreads holding features apart sufficiently to release the stylet shaft 3102 and spring 3410. The disengagement can also occur by means of a rotary intermediate device that turns such that the stylet shaft 3102 and spring 3410 lose engagement and are allowed to be biased proximally. In this embodiment, the stylet sharp tip 3104 is never advanced for very long and inadvertent advancement of the structure has less risk of causing damage to critical tissues because the sharp stylet tip 3104 retracts faster than a human can push the device forward.

In yet other embodiments, the hub of the steerable transseptal needle can comprise a side port that is operably connected to the central lumen of the steerable transseptal needle. This side port can be terminated with a female Luer lock and optionally a hemostasis valve or stopcock. This side port can be used to inject or withdraw fluids or to measure pressure while the piercing stylet system is in place and locked onto the proximal end of the steerable transseptal needle.

FIG. 37 illustrates a top view of a steerable transseptal needle hub body 3708 affixed to a three-way stopcock 3700. The stopcock 3700 comprises a side port 3702 further comprising a lumen (not shown), which is operably connected to the other lumens of the stopcock through the petcock 3712, which allows both the side port 3702 and the proximal through port 3710 to be operably connected to a central lumen (not shown) of the hub 3708. The ends of the stopcock lumens are preferably female Luer lock ports, but could also be regular threaded mounts, quick connects, bayonet mounts, or the like. The piercing stylet hub 3500 is affixed to the Luer threads of the proximal through port 3710.

FIG. 38 illustrates a side view of a faceted sharp distal end 3800 of a piercing stylet 3102. Also illustrated in FIG. 38 are the outer tube 3106 and the blunted, generally laterally cut and rounded distal end 3110 of the outer tube. The number of facets can range from 1 to 10 or more with a preferred number of 2 to 4. Where the stylet tip is not faceted, it can comprise a simple cone or bevel as illustrated elsewhere. The facets can be cut at an angle of between about 5 and about 45 degrees relative to the longitudinal axis of the stylet 3102.

FIG. 39A illustrates a side, partial breakaway view of a steerable transseptal needle comprising a piercing stylet 3900 further comprising a distal shaft 3902, the sharp stylet tip 3104, a transition zone 3904, a cutout or cutaway section 3908, and a central shaft 3902. The steerable transseptal needle comprises the inner tube 3106, the outer tube 3112, and the blunted distal end 3110 of the inner tube 3106, and one or more, optional, fenestration, window, opening, or hole 3910. The cutaway region 3908 can run the entire length of the stylet wire or it can terminate at a transition, as shown, to a substantially, completely rounded distal end 3902. The cutaway region 3908 can project out the distal end of the inner tube 3106 or it can fully reside within the inner tube 3106 when retracted, extended, or both. The window 3910 can permit pressure measurement and fluid injection or removal therethrough when operably in communication with the cutaway region 3908.

FIG. 39B illustrates a lateral cross-section of a stylet wire 3900 configured to facilitate fluid flow or pressure measurement while the stylet wire 3900 is in place within the lumen of a steerable transseptal needle. The stylet wire 3900 has had its cross section reduced thus creating a half-moon shaped shaft and creating a half-moon shaped lumen 3908 within the inner tube 3106. The cross-section can be half-

45

moon shaped, as illustrated, or it can be C-shaped, S-shaped, D-shaped, U shaped, or the like.

FIG. 40 illustrates a hub of a steerable transseptal needle safety piercing stylet wherein the hub of the stylet comprises a quick release to actuate, and then retract the stylet. The stylet hub 4000 comprises a push button 4002, a first transmission arm 4004 further comprising a first magnet 4006, a second transmission arm 4008 further comprising a second magnet 4010 and a catch 4030, a stylet hub body 4012 further comprising a stop 4018, a stylet wire 4016 and a return spring 4014. The hub 4020 of the steerable transseptal needle further comprises an electrical connector 4022, operably connected to the inner tubing 4024 or its anchor 4026. The outer tube of the needle is covered with an insulating jacket 4028. The apparatus may also include a pressure jacket disposed exterior to the outer tube wherein the pressure jacket prevents ingress or egress of fluid through the fenestrated wall of the apparatus.

The stylet wire 4016 is affixed to the first transmission arm 4004. First magnet 4006 is affixed to the first transmission arm 4004 and the second magnet 4010 is affixed to the second transmission arm 4008. The return spring 4014 is operably connected to the first transmission arm 4004 to bias the first transmission arm 4004 proximally away from the second transmission arm 4008. The first 4004 and second 4008 transmission arms as well as the spring 4014 reside with, and are radially constrained within a cavity within the stylet hub body 4012. The spring 4014, as well as the first and second transmission arms 4004 and 4008 can move longitudinally within the cavity of the stylet hub body 4012. The spring 4014 is affixed at one end to the stylet hub body 4012 and to the second transmission arm 4008 such that the spring 4014, at rest, is uncompressed and distal movement of the second transmission arm 4008 forces the spring 4014 into compression from which it wants to recover. The spring 4014 can also be used in tension using an alternative layout. The stop 4018 within the stylet hub body 4012 prevents unwanted distal motion of the second transmission arm 4008 because of the stop 4030 interferes with the catch 4030. This interference forces the first and second transmission arms and their magnets 4006 and 4010 apart after a predetermined travel.

The magnets 4010 and 4006 can comprise materials such as, but not limited to, samarium cobalt, neodymium iron boron, iron, or the like. The magnets can comprise magnifier structures to optimize the magnetic fields. The magnets can be configured, in a preferred embodiment, so that opposite poles come together to provide attraction between the magnets, or wherein like poles come together to provide for repulsive forces.

The electrical connector 4022 is integral or affixed to the anchor 4026 or it can be operably connected and affixed to another metal component, such as the jackscrew traveler (not shown). Application of electrical RF power to the electrical connector 4022 is in electrical communication with the inner tube 4024. A separate ground wire can be applied to the patient. The electrical insulator jacket 4028 is optional but is preferably affixed around the outer tube for its full length or substantially so. Thus, the inner tube 4024 ultimately receives the RF energy and is the component that can burn or cauterize tissue. The inner tube 4024 can be blunted, partially, or completely closed off at its distal end to render it maximally atraumatic.

FIG. 41 illustrates a steerable needle or axially elongate medical device 4100 comprising a hub 4112, a fluid injection sideport 4102, a stopcock 4104, a first control rod 4106, a second control rod 4108, a proximal port 4110, a piercing

46

stylet 3500, an outer tube 4114, a control knob 4116 further comprising a pair of internal threads, an outer tube anchor 4118, an inner fluid tube or sleeve 4120, a second jackscrew traveler 4122, a first jackscrew traveler 4124, and an optional drive system 4126.

Referring to FIG. 41, the first control rod 4106 and the second control rod 4108 are slidably, axially movably, constrained within the outer tube 4114 and extend to or beyond the end of a distal bendable region of the outer tube 4114 (not shown). The outer tube is affixed to the outer tube anchor 4118. The fluid-tight sleeve 4120 is a tube that is constrained within the first control rod 4106 and second control rod 4108. The proximal end of the fluid tight sleeve 4120 is operably connected to the sideport 4102 and the proximal port 4110 and is affixed to the hub 4112. The distal end of the fluid tight sleeve 4120 terminates at or near the distal end of the device 4100. The hub 4112 is affixed or integral to the stopcock 4104. The proximal end of the first control rod 4106 is affixed or integral to the first jackscrew traveler 4124 and the proximal end of the second control rod 4108 is affixed or integral to the second jackscrew traveler 4122. The first jackscrew traveler 4124 comprises external threads that comprise a right hand helix. The second jackscrew traveler 4122 comprises external threads that comprise a left-hand helix. The control knob 4116 comprises distal and proximal extensions that further comprise internal threads configured to engage with the threads on the jackscrew travelers 4122 and 4124. Thus, the distal threads on the control knob 4116 comprise a right hand helix and the proximal threads on the control knob 4116 comprise a left hand helix. The threads can, of course be reversed so that the proximal threads are right hand helices and the distal threads are left hand helices. The two control rods 4106 and 4108 and their jackscrew travelers 4124 and 4122 can also be controlled with separate control rod. However, the configuration illustrates provides for a push-pull arrangement that allows a single control movement to actuate the control rods for simplest operation. The actuator 4126 can comprise a stepper motor and controller, a geared actuator, hydraulic pistons, pneumatic pistons, linear motor, and the like.

FIG. 42A illustrates a steerable medical device 4200, in its straight, unarticulated configuration, comprising a hub 800, a distal tip 4210, a distal bendable region 4202, a proximal bendable region 4204, a non-bendable intermediate region 4206, and a non-bendable proximal region 4208.

Referring to FIG. 42A, the inner control rods or rods and keepers (not shown) preferably run substantially at least the entire length of the bendable regions 4202, 4204, and the intermediate non-bendable region 4206. The proximal bendable region 4204 comprises two T-slots which are configured so that the lateral cuts in the outer tube close down and increase flexural modulus in that area. The intermediate non-bendable region 4206 retains a high flexural modulus. The distal bendable region 4202 is configured with seven T-slots but this number can vary between 1 and 20 with a preferred number of between 4 and 15. The width of the laterally formed slots can be adjusted so as to maximize bending strength or flexural modulus. The T-slots in the proximal bendable region 4204 are approximately 0.003 inches wide but can range from about 0.001 inches to about 0.020 inches with a preferred range of about 0.001 to about 0.010 inches, in the case of a 0.050-inch outer tube outside diameter.

In order to maintain maximum resistance to prolapse when the bent or articulated needle is forced against the septum, the slot widths and numbers should be configured such that the tube will not articulate beyond about 90

degrees and preferably less than about 85 degrees and most preferably less than about 80 degrees. The narrower t-slots (about 0.002 to 0.003 inches) are beneficial in that they reduce the occurrence of yield in the outer tube relative to that which would occur with wider t-slots, for example 0.009 inches wide, under high deflection bending.

FIG. 43A illustrates a steerable needle or catheter comprising a cutting stylet 4300. The cutting stylet 4300 is illustrated with its cutting element retracted so as not to extend radially outward beyond the boundary of the cutting stylet 4300. The steerable needle or catheter comprises the outer tube 4204, the distal end of the inner tube 4208, the distal tip 4210 of the inner tube 4208, a cutting stylet tube 4302 further comprising a cutting stylet lumen 4318, a proximal cutting stylet wire 4304, a sharp cutting wire segment 4308, a cutting stylet tube window 4316, a cutting stylet wire distal end 4310, a sharp distal tip 4314 of the cutting stylet tube 4302, and a distal weld 4312.

FIG. 43B illustrates a steerable needle or catheter comprising a cutting stylet 4300. The cutting element is illustrated as advanced or activated radially outward so as to cut a larger incision in tissue than is possible with an axially elongate stylet. The steerable needle or catheter comprises the outer tube 4204, the distal end of the inner tube 4208, the distal tip 4210 of the inner tube 4208, the cutting stylet tube 4302 further comprising the cutting stylet lumen 4318, the proximal cutting stylet wire 4304, the sharp cutting wire segment 4308, the cutting stylet tube window 4316, the cutting stylet wire distal end 4310, the sharp distal tip 4314 of the cutting stylet tube 4302, and the distal weld 4312.

The cutting wire 4304 is actuated by distal advance of the cutting stylet wire 4304 by actuation at the proximal end of the cutting stylet system 4300. The weakened portion or segment 4308 selectively bends and the window 4316 assists in guiding weakened portion 4308 radially outward in a predictable direction. The cutting stylet system 4300 can be fabricated from stainless steel, nitinol, titanium, cobalt nickel alloy, or the like. The cutting stylet system 4300 can further comprise radiopaque markers to assist with visualization of its operation and extent of position and advancement.

The cutting stylet 4300 can be actuated radially outward and it can be retracted radially inward and stowed for subsequent maneuvers including advancement and withdrawal from the patient.

FIG. 44A illustrates the distal end of a steerable transseptal needle 4400 further comprising a cutting stylet tube 4402, a window 4406 in the cutting stylet tube 4402, an actuator element 4404 further comprising a sharp distal tip 4408, at least one expandable sharp elements 4412 and 4414, the steerable transseptal needle distal end 4210, the distal tubing projection 4208, and the outer tube 4204. The control or actuator element 4404 is advanced and thus, the at least one expandable sharp elements 4412 and 4414 are not radially expanded because the distal end 4410, to which they are attached is advanced distally.

The expandable sharp elements 4412 and 4414 can number from about 1 to about 10 with a preferred number of between about 2 and about 4. The expandable sharp elements 4412 and 4414 are affixed at their distal end to the distal tip 4410 or a length of tubing affixed thereto. The expandable sharp elements 4412 and 4414 are affixed, or integral, at their proximal end to the cutting stylet tube 4402. The expandable sharp elements can comprise malleable materials, spring biased materials, or shape memory materials. Materials of manufacture of the expandable sharp elements 4412 and 4414 can include but not be limited to,

nitinol, titanium, stainless steel, tantalum, gold, platinum, platinum iridium, and the like, the latter four of which include enhanced radiopaque properties.

FIG. 44B illustrates the distal end of the steerable transseptal needle 4400 further comprising the cutting stylet tube 4402, the window 4406 in the cutting stylet tube 4402, the actuator element 4404 further comprising the sharp distal tip 4408, the expandable sharp elements 4412 and 4414, the steerable transseptal needle distal end 4210, the distal tubing projection 4208, and the outer tube 4204. The control or actuator element 4404 is retracted, thus pulling the distal end 4410 proximally and thus, the at least one expandable sharp elements 4412 and 4414 are radially expanded. The at least one expandable sharp elements 4412 and 4414 are configured with sharp exterior edges capable of cutting animal tissue.

The advantage of this system 4400 is that it cuts an incision in tissue and not a puncture hole. The incision is capable of superior healing to a puncture hole and is also capable of expanding to permit passage of larger instruments than would a puncture hole, especially in fibrous or scarred tissue.

FIG. 45 illustrates a steerable transseptal needle 4500 comprising the inner tube 4208, the outer tube 4204, and a piercing stylet system further comprising a core structure 4502, a first cutting element 4506, a second cutting element 4508 and at least one cutting edge 4510 disposed on the exterior of one or all of the cutting elements 4506 and 4508. The cutting elements 4506 and 4508 are separated by the gap 4504 which permits movement of one cutting element 4506 in a direction different from that of the other cutting element 3508.

There can be one cutting element, two cutting elements as shown, or more. Some or all of the cutting elements can comprise the sharpened edge 4510. The cutting elements 4506 and 4508 can be fabricated from materials such as but not limited to, nitinol, stainless steel, nitinol, and the like. Nitinol elements can be superelastic or shape memory in performance.

The core structure 4502 translates longitudinally and slides within the inner tube 4208. The core structure 4502 can be manipulated by a user since it extends from the proximal end of the steerable transseptal needle 4500 to the expandable cutting elements 4506 and 4508. Retraction of the core structure 4502 can retract the cutting elements 4506 and 4508 within the inner tube distal end 4210 completely. Advancement of the core structure 4502 exposes the cutting elements 4506 and 4508 beyond the distal end 4210 and allows them to spring or move radially outward to cut an incision larger than the diameter of the core structure 4502, itself. The core structure can comprise a solid wire, tubular, or other cross-section.

FIG. 46 illustrates the proximal end of a steerable transseptal needle 4600 comprising a hub 4602, a power supply 4604, a radiofrequency generator 4606, a switch 4608, a control knob 4610, an inner tube 4622, an outer tube 4624, an insulating cladding 4612, an adapter 4620 further comprising a side port 4614, a stopcock 4616 and a proximal port 4618.

The power supply 4604 can comprise batteries or it can be wired to an external source of electrical power. The radiofrequency (RF) generator 4606 is powered by the power supply 4604 by way of a bus (not shown) and can be turned on or off with the switch 4608. The output of the radiofrequency generator 4606 can be monopolar or bipolar and is operably connected to the outer tube 4624, the inner tube 4622, or both. The insulating cladding 4612 surrounds the

outer tube **4624** and can also surround the projecting part of the inner tube **4622** leaving a small region at the distal tip of the inner tube **4622** uninsulated so that the electrical energy can be applied to tissue for cutting or cauterizing purposes. In the case of a monopolar system, the patient can have an electrode affixed to their skin, usually on their back to form a closed circuit. The insulating cladding **4612** can be fabricated from materials such as, but not limited to, polyester, fluoropolymers, and the like. The steerable transseptal needle **4600** can be useful in cutting through scarred tissue that resists normal needle punctures. The power supply can be integral to the system **4600**, as illustrated, or it can be external and wired to inner **4622** or outer tube **4624** through a bus residing within the hub **4602**.

FIG. 47A illustrates a piercing stylet **4700** comprising an axially elongate tube **4702**, a central lumen **4706**, a sharp distal tip **4710**, a radiopaque marker **4704**, distal side openings **4708**.

The radiopaque marker **4704** is encapsulated within the distal end of the stylet tube **4702** to minimize the risk of being dislodged. The radiopaque marker **4704** can be welded, silver soldered, crimped, swaged, bonded, or otherwise fastened, to the stylet tube **4702**. The side openings or windows **4708** comprise perforations that permit fluid communication between the central lumen **4706** and the exterior of the tubing **4702**. The radiopaque marker **4704** preferably resides distal to the one or more side windows **4708**. The radiopaque marker **4704** can comprise a cylindrical rod, or other geometric shape, of materials such as, but not limited to, platinum, tantalum, platinum iridium, gold, barium or bismuth compounds, and the like. The stylet tube **4702** can be swaged or crimped at its distal end to cover the radiopaque marker **4704**, to grip a depression in the radiopaque marker **4704**, or both, to prevent dislodgement of the radiopaque marker **4704** from the tube **4702**. The distal end of the stylet tube **4702**, following having been reduced in diameter, can be further welded to provide material for creating the sharp tip **4710**. The tube **4702**, the marker **4704**, or both, can be ground or otherwise formed into a sharp tip with, for example, a conic, a faceted trocar, a bevel, or the like.

Fluid injected through the central lumen **4706** can escape the central lumen through the side windows, ports, or fenestrations **4708**. Furthermore, the side windows **4708** can allow for pressure measurement by means of a pressure transducer operably connected to the central lumen **4706** at the proximal end of the stylet or another location.

FIG. 47B illustrates the piercing stylet **4700** comprising the tube **4702**, further comprising the central lumen **4706** and a tubing wall **4712**, the hub **3500**, and one or more proximal windows **4714** to allow for fluid communication between into the piercing stylet central lumen **4706** from an exterior port (not shown), which can, for example, be affixed and operably connected to a hub (not shown) of a transseptal needle (not shown). The one or more windows **4714** can be formed into the tubing wall **4712** by standard machining methods, such as, but not limited to, laser cutting, EDM, standard milling, photochemical etching, or the like.

Use of the system, as illustrated in FIGS. 47A and 47B, allows the central lumen of a transseptal needle to contain a large cutting or piercing stylet without compromising the ability to measure pressure, inject fluid or withdraw fluid from a patient. The radiopaque marker **4704** further permits the operator to visualize the distal-most cutting part of the system under fluoroscopy, which enhances the ability to prevent the system from cutting unwanted perforations in the patient's anatomy.

FIG. 48A illustrates a proximal end of a steerable transseptal needle **4800**, in partial side cross-section, wherein the steerable transseptal needle **4800** comprises an inner tube **4804**, an outer tube **4802**, a hub **4806**, a control knob **4808**, a jackscrew traveler **4810**, a spring **4812**, an O-ring **4814**, an O-ring retainer **4816**, an inner tube anchor **4818**, a hub to stopcock adapter **4820**, and a stopcock **4822** (not sectioned).

The jackscrew traveler **4810** comprises threads on its exterior that engage internal threads within the control knob **4808**. The jackscrew traveler **4810** is keyed such that it cannot rotate within the hub **4806**. Thus rotation of the control knob **4808** causes the jackscrew traveler **4810** to advance either proximally or distally. In the illustrated embodiment, the jackscrew traveler **4810** engages three threads within the control knob **4808**. Rotation of the control knob **4806** in a first direction causes the jackscrew traveler **4810** to advance distally. The outer tube **4802** is affixed to the jackscrew traveler and thus moves distally relative to the inner tube **4804**, which is affixed to the anchor **4818**, which is affixed to the hub **4806** and the adapter **4820**. Rotation of the control knob **4808** in a second direction causes the jackscrew traveler **4810** to move proximally relative to the inner tube **4804**. Since only three threads are engaged, once the jackscrew traveler **4810** moves three thread pitches proximally, its threads disengage from the threads of the control knob **4808**. Further rotation of the control knob **4808** does not result in any further proximal movement of the jackscrew traveler **4810**. Rotation of the control knob **4806** in the first direction, following thread disengagement, causes re-engagement of the threads of the jackscrew traveler **4810** to the threads of the control knob **4808**, coerced by the spring **4812**, which has become increasingly compressed by the proximal motion of the jackscrew traveler **4810**. This system is advantageous relative to a hard stop because the jackscrew traveler **4810** and control knob **4808** generate a large mechanical advantage that could rip the hub **4806** and the adapter **4820** apart in the situation where a hard stop, or motion limiter, is employed.

FIG. 48B illustrates the proximal end of the steerable transseptal needle **4800**, in top view, wherein the steerable transseptal needle **4800** comprises the inner tube **4804**, the outer tube **4802**, the hub **4806**, the control knob **4808**, the hub to stopcock adapter **4820** further comprising the side port **4824** and a sealing cap **4826**, and the stopcock **4822** further comprising the proximal through port **4828**. The proximal through port **4828** and the side port **4824** are in fluid communication with each other but can be separated by the stopcock **4822**, as shown in the illustrated embodiment.

FIG. 49A illustrates a side view of a Side Window Introducer system **4900**, configured to deliver a steerable endoluminal punch or needle, in partial cutaway section. The Wide Window Introducer system **4900** comprises a sheath **4902**, a dilator **4904** a sheath side window **4906** and a dilator side window **4908**.

The sheath **4902** comprises the side window **4906**. The dilator **4904** also comprises the side window **4908**. Both windows **4906** and **4908** can be aligned so that the needle **4910** can bend out of the longitudinal axis.

FIG. 49B illustrates a side view of the introducer system **4900** in partial breakaway view, wherein a steerable endoluminal punch or needle **4910** has been inserted and resides with its distal end within the area of the windows **4906** and **4908**. The needle **4910** tip can be aligned such that the entire bendable region of the needle **4910** or a portion thereof are within the windows **4906** and **4908** and thus permitted to articulate to at least some degree.

## 51

FIG. 40C illustrates the steerable endoluminal punch or needle 4910 being articulated out through the side windows 4906 and 4908. With the sheath 4902 and dilator 4904 positioned within a body vessel, the sheath can provide a backstop to permit the needle 4910 to be pushed laterally against tissue to effect a perforation. Having both the region distal to, and proximal to, the bendable region of the needle 4910 provides for more backstop than if just the region proximal to or distal to the needle 4910 are secured against a wall of a body vessel or lumen.

In other embodiments, the sheath 4902 and the dilator 4904 can be inserted into the body lumen and the dilator 4904 can be removed from the lumen of the sheath 4902 before inserting the needle 4910. In this embodiment, the needle 4910 bendable region need be aligned within the sheath window 4906 without worry about alignment of the dilator window 4908. Such alignment can be controlled, of course, at the hub end of the sheath 4902 and dilator 4904 with alignment keys or rotational positioning devices as well as longitudinal stops or keys.

FIG. 50A illustrates a steerable endoluminal punch or needle 5000 comprising an outer tube 5004, a composite inner tube and pull rod 5002, which further comprises a lumen 5006, an end cap comprising a sharp tip 5008, a hinge region 5012, and a gap 5010.

The hinge 5012 connects the inner tube 5002 to the end cap 5008 and permits rotational motion about the axis of the hinge while retaining the end cap 5008 firmly affixed to the inner tube 5002 distal end.

FIG. 50B illustrates the punch 5000 of FIG. 50A wherein a stylet 5014 or other control rod has been inserted into the lumen 5006 (See FIG. 50A) such that the stylet distal end resides adjacent the sharp, hinged end cap 5008.

FIG. 50C illustrates the punch 5000 of FIG. 50B wherein the stylet control rod 5014 has been advanced distally bending the hinge 5012, widening the gap 5010, and causing the sharp tip of 5008 to be more distally forward oriented such that the sharp tip of 5008 is now in a configuration to cut tissue upon application of distal axial movement than in its non-bent condition of FIGS. 50A and 50B. The hinge 5012 can be a flexible strip of metal, polymer, etc. or it can comprise a pin and interlocking receivers for each side. The hinge 5012 can be spring biased, magnetically biased, or the like. The end cap, or any of the other structures, can further comprise radiopaque markers (not shown) such as, but not limited to, tantalum, platinum, platinum iridium, gold, barium sulfate, and the like.

FIG. 51A illustrates a first step in generating a sharp distal end on a tissue punch 5100 comprising an outer tube 5104, an inner tube 5102, and a truncated conical region 5106 at its distal end 5108.

The conical region traverses from the OD of the tube to the ID of the tube and provides increasing sharpness by minimizing the remaining wall thickness at the distal end. This reduced wall thickness also reduces any shoulders that might be forced against tissue to be perforated and might therefore resist said tissue perforation. Ideally, the distal remaining wall thickness is approximately 0.001 or less.

FIG. 51B illustrates a second step in generating a sharp distal end on a tissue punch 5100 comprising the outer tube 5104, the inner tube 5102, a bevel 5110, the truncated conical region 5106, and a rounded, dulled heel region 5112.

The angle of the bevel 5110 can range between about 50 degrees and about 10 degrees with a preferred angle range of about 40 and 25 degrees.

FIG. 52 illustrates the distal end of a steerable endoluminal punch 5100 comprising the outer tube 5104, the inner

## 52

tube 5102, the heel 5112, the conic section 5106, the sharp tip 5108, and a blunt protective stylet 5202 further comprising a blunt, rounded end 5204, and a hub (not shown). The blunt protective stylet 5202 need not project too far out the front of the distal end of the punch 5100 because it could cause procedural problems, if too long. The blunt protective stylet 5202 can project between about 1 mm and about 10 mm with a preferred range of about 2 mm to about 6 mm. Larger diameter stylets 5202 present a reduced gap between the stylet and the point of the needle and are thus, more protective than smaller diameter stylets 5202.

FIG. 53 illustrates a section of a human heart 5300 comprising a left atrium 5308, a superior vena cava 5304, a right atrium 5302, an inferior vena cava 5306, and an interatrial septum 5301. Also illustrated are the introducer sheath system 4900 and the steerable endoluminal punch 4910 of FIG. 49C.

Access can be gained through a subclavian vein or a jugular vein. The introducer sheath system 4900 can be routed over a guidewire, which is then replaced with the endoluminal punch 4910. After the endoluminal punch passes into the left atrium of the heart through the interatrial septum 5310, a guidewire (not shown) can be passed through the central lumen of the punch 4910 and be routed into the left atrium 5308 to establish a pathway thereto.

Superior access, through the superior vena cava, to the left side of the heart entails use of a shorter catheter than access from the inferior direction (through a femoral vein and the inferior vena cava). However, the geometries are such that the device needs to be angled quite more than in the inferior approach. Thus a puncture device that is able to articulate to about 90 degrees or more is beneficial. Furthermore the puncture device needs to be able to generate lateral forces on the atrial septal wall after turning this sharp angle, and this using generally axial movement on the part of the physician operator. The Side Window Introducer 4900 provides a backbone against which a puncture device, such as the Steerable Endoluminal Punch 4910, can push. Additional stiffness can be added to the Side Window Introducer 4900 such as, but not limited to, support bars, metal components in the sheath 4902 or dilator 4904, or radially enlargeable components such as balloons, expandable metal or plastic, or the like. This additional stiffness can be added after placement of the Side Window Introducer to permit flexibility in access to a treatment site, in this case the interatrial septum 5310. The Side Window Introducer can further comprise ultrasound capability to provide for imaging at the point of treatment. Such ultrasound capability can include 2-D or real time 3-D imaging.

FIG. 54A illustrates the distal end of a steerable endoluminal punch comprising an outer tube 5400 further comprising a plurality of radially oriented slots 5410, optionally comprising strain reliefs on each slot. The punch 5400 further comprises an inner tube 5402, a 4 pointed crown distal end 5406, and sharpened edges of the crown 5408.

FIG. 54B illustrates the distal end of a steerable endoluminal punch comprising an outer tube 5420 further comprising the plurality of radially oriented slots 5410, optionally comprising strain reliefs on each slot. The punch 5420 further comprises an inner tube 5422, a 2 pointed crown distal end 5426, and sharpened edges of the crown 5428. Note that in FIG. 54B, the T-slot is oriented 90 degrees toward the viewer relative to its orientation in FIG. 54A. The steerable endoluminal punch 5420 articulates within the plane of the paper in FIG. 54A, whereas the steerable

endoluminal punch **5420** articulates up out of the plane of the paper in FIG. **54B**. The illustrated orientations are preferred embodiments.

The distal end of the steerable endoluminal punch can comprise any number of points between 1 and about 10 but more preferably between about 1 and about 4. Another embodiment comprises a distal end having a three-pointed crown (not shown). The blunt stylet **5202** (see FIG. **52**) can be used to shield the sharp crown points from the walls of a catheter or dilator through which it might be passed.

FIG. **55** illustrates the distal end of a steerable endoluminal punch system **5500** comprising a cutting stylet **5502**, further comprising a sharp tip **5504**, one or more laterally biased cutting blades **5506** further comprising one or more sharp edges **5508**, the inner tube **5402**, the outer tube **5404** further comprising a plurality of radially oriented slots **5410**, a hub (not shown) at the proximal end which may or may not be spring loaded, and a distal end **5408** comprising one or more sharp edges **5406**. In the illustrated embodiment, the two cutting arms **5506** are able to be squeezed together for insertion into the lumen of the inner tube **5402** by the user. The arms **5506** are biased outward so that when advanced beyond the end of the inner tube distal end **5408**, they can spring outward (or be forced outward with a control rod) to cut a larger incision in tissue than would be possible with the native diameter of the cutting stylet **5502**. This embodiment is especially useful for cutting a sufficiently large incision through which to pass the inner tube **5402**, the outer tube **5404**, and any sheaths and dilators disposed thereover, especially in very elastic tissue, scar tissue, or thickened tissue.

A primary issue with an endoluminal punch, or needle, is that it generally creates an incision or hole in tissue through which a catheter, dilator, or other axially elongate instrumentation is to be advanced. Creation of an incision that is large enough for the endoluminal punch to pass, does not guarantee that larger diameter devices riding over or on the endoluminal punch will be able to pass through this small incision or hole. Thus, it can be beneficial, or even mandatory, to create an incision that is larger than that needed for a sharp stylet and larger than that needed for the endoluminal punch to pass through the hole so that a catheter, dilator, or combination thereof, to pass through the hole. The expanding sharp stylet can accomplish this. Application of electrical energy, such as radiofrequency energy, at the tip of the endoluminal punch can perform this hole enlargement by weakening the tissue in a tissue penumbra around the needle tip. This is especially important when the tissue is scarred, thickened, or extremely elastic. Punching a hole in such tissue and then dilating that hole up to a larger diameter by tapered dilators can stretch the tissue and locally increase its resistance to further penetration. An introducer comprising a small cutting element at its distal end, near or on the dilator taper region, can provide for additional tissue incision and permit the larger diameter catheter and dilator to pass through an enlarged incision. The cutting element on the introducer or its dilator can be operated from the proximal end through use of a control rod or wire or by selective use of the blunt stylet, a cutting stylet, or both, such that the cutting element stays retracted and is only activated when desired, by user control.

FIG. **56A** illustrates a cutting introducer **5600** comprising a sheath **5602**, a tapered dilator **5604** further comprising a secondary lumen **5606**, through which is slidably inserted a cutting instrument **5608**. The tapered dilator **5604** further comprises a central lumen through which is slidably and removably inserted an endoluminal punch **5610**. The

endoluminal punch **5610** further comprises a small diameter distal tubing projection **5612** tipped with a sharp end **5614**. Also illustrated is a piercing stylet **5616** further comprising a sharp trocar distal tip **5616**, which is slidably inserted through a central lumen of the endoluminal punch **5610**. The cutting instrument **5608** is configured to be selectively advanced, when needed, to assist with cutting an incision bigger than that which can be cut by the sharp end **5614** and the piercing stylet **5616**.

FIG. **56B** illustrates a cutting introducer **5630** further comprising the introducer sheath **5602**, a dilator **5624** further comprising a cutting element lumen **5622** and a cutting element **5620**. An endoluminal punch **5610** is inserted into a central lumen of the dilator **5624**. The optional piercing stylet **5616** is inserted through a central lumen of the endoluminal punch **5610**. Distal end of the larger diameter portion of the endoluminal punch **5610** is configured to engage the proximal end of the cutting element **5620** and force it distally thus exposing its distal sharp end to assist with tissue incision. The cutting element **5620** is trapped within the cutting element lumen **5622** and cannot be removed from the system. The cutting element **5620** is preferably biased in its retracted position by a spring (not shown) or other biasing element.

The steerable needle, in other embodiments, can comprise monitoring systems to measure, display, announce, record, or evaluate operating parameters of the steerable transseptal needle. In an embodiment, the steerable transseptal needle can comprise strain gauges to measure the force being applied by the user to bend the needle. A torque gauge can also be comprised by the system to measure torque being applied to the control knob or the torque being applied by the distal curvature movement. The strain gauge or torque gauge can be affixed within the hub or elsewhere within the steerable transseptal needle to measure compression or tension forces. This information can be displayed in the form of a readout device, such as a digital display of the force or torque. The number of turns can be counted and displayed by, for example, a Hall-Effect sensor, mechanical counter, or the like. In an embodiment, the force or torque can be correlated to the angle of deflection at the distal end, the number of turns applied to the control knob, or both. The readout can be digital or analog and can be affixed to the hub or can be wirelessly received and displayed on external equipment such as a smart phone, computer, tablet computer, panel display, or the like. The wireless technology can, for example, comprise Wi-Fi, Bluetooth®, or other standardized protocols. The human interface can, in other embodiments, comprise audible feedback such as a simple beep or tone, or it can be more sophisticated and provide information using language callouts such as force, turns, torque, or the like.

In operation, the system operates similarly to the standard steerable transseptal needle with a few exceptions. The procedure is to advance a steerable transseptal needle, with a tissue piercing stylet affixed in place, through a transseptal introducer that has already been placed. The steerable transseptal needle is articulated to generate the proper curve, as determined under fluoroscopic or ultrasound guidance. The steerable transseptal needle transseptal introducer assembly is withdrawn caudally out of the superior vena cava and into the right atrium of the heart. Proper location, orientation, tenting, and other features are confirmed. Radiopaque dye can be injected through the steerable transseptal needle to facilitate marking of the fossa ovalis or blood flow around the distal end of the steerable transseptal needle. Pressure measurements can also be taken through the lumen of the

steerable transseptal needle to confirm tracings consistent with the right or left atrium of the heart. Once proper positioning has been confirmed, a safety is removed from the stylet hub and a button on the stylet hub is depressed or actuated to cause the sharpened stylet tip to advance out beyond the distal end of the steerable transseptal needle. This sharpened stylet punches through the fossa ovalis and the septal tissue pulls over the stylet, over the inner tube, and over the obturator or dilator of the transseptal introducer. At this point, the sharp stylet is released and retracts proximally within the steerable transseptal needle. The transseptal introducer is now within the left atrium of the heart and the steerable transseptal introducer can be withdrawn from the lumen of the obturator.

The present invention may be embodied in other specific forms without departing from its spirit or essential characteristics. The described embodiments are to be considered in all respects only as illustrative and not restrictive. For example, the deflecting wires **412** can be replaced by an electromechanical actuator and external control unit. Control over forces applied to the hub, including relative force application to the inner and outer tubes and control rods and rotation of the system about its longitudinal axis can be controlled by electromechanical actuators and computerized controllers, or the like.

We claim:

**1.** An apparatus adapted for punching a hole in a body lumen or hollow organ of a mammal comprising:

- an outer axially elongate hollow tube having a proximal end, a distal end, a longitudinal axis, and a lumen extending therethrough;
- an inner tube divided, axially, into at least one control rod and a partially disconnected keeper within a specified bendable region;
- a plurality of laterally oriented slits extending partway into the outer tube within the bendable region but not completely transecting the outer tube;
- a hub affixed to the proximal end of the inner tube, wherein the hub comprises an internal lumen capable of receiving a control mechanism, wherein the outer tube is constrained not move relative to the hub; and
- a connection between the inner tube and a point of the outer tube distal to the plurality of laterally oriented slits in the bendable region.

**2.** The apparatus of claim **1** further comprising a short, rounded, removable, protective stylet projecting out a distal end of the inner tube to shield surrounding structures from a sharp distal end of the apparatus.

**3.** The apparatus of claim **1** further comprising a removable piercing stylet capable of punching through tissue more sharply than a native distal end of the apparatus.

**4.** The apparatus of claim **3** wherein a distal end of the piercing stylet is capable of expanding radially outwardly to increase the size of an incision created by the apparatus.

**5.** The apparatus of claim **1** wherein the distal end is formed into a crown configuration comprising at least two sharp points.

**6.** The apparatus of claim **1** wherein the distal end comprises a conical configuration to minimize wall thickness at a tip of the outer tube and bring a sharp region radially inward away from the walls of a catheter or dilator through which it can be introduced.

**7.** The apparatus of claim **6** further comprising a bevel to generate a sharp distal point located radially inward from an outside diameter of the inner tube.

**8.** The apparatus of claim **6** further comprising at least two points configured as a crown.

**9.** The apparatus of claim **1** further comprising a distal tip which is movable from a first blunt configuration to a second sharp configuration by action of a user at a proximal end of the apparatus.

**10.** The apparatus of claim **9** wherein a control rod is configured to move the distal tip from the first blunt configuration to the second sharp configuration and further comprises a lumen for flow of fluids or pressure measurement.

**11.** The apparatus of claim **1** further comprising a Side Window Introducer comprising an axially elongate sheath and an axially elongate dilator configured to slidably and removably engage the sheath, wherein the sheath and the dilator comprise at least one side window proximate their distal end, further wherein the side windows of the sheath and dilator can be aligned with each other to provide a side port through which the apparatus of claim **1** can articulate out of the longitudinal axis.

**12.** The apparatus of claim **1** wherein the distal end can controllably curve between about 0 and at least about 90 degrees from the longitudinal axis.

**13.** The apparatus of claim **1** further comprising a pressure jacket disposed exterior to the outer tube wherein the pressure jacket prevents ingress or egress of fluid through a fenestrated wall of the apparatus.

**14.** The apparatus of claim **1** further comprising an innermost tube, further comprising a proximal end, a distal end, and a lumen therethrough, disposed interior to the outer tube and preventing the ingress or egress of fluid from the lumen of the outer tube.

**15.** The apparatus of claim **1** further comprising one or more radiopaque markers capable of enhanced visibility under fluoroscopy.

**16.** The apparatus of claim **1** wherein relative forces generated on the inner tube and outer tube are determined by commands generated by a computer or robotic device and delivered by a force generating mechanism coupled to the computer or robotic device.

**17.** The apparatus of claim **1** wherein further comprising a fluid flow channel around or within a sharpened stylet, the fluid flow channel being operably connected to a port on the hub of the apparatus.

**18.** The apparatus of claim **1**, further comprising a central stylet that is sharpened and configured to punch tissue, said stylet being constrained within a lumen of the inner tube to be retracted within the inner tube until activated.

**19.** The apparatus of claim **1** wherein a distal end of the inner tube is blunted and tapered into a conic shape.

**20.** The apparatus of claim **1** wherein a stylet hub is affixed to a proximal end of a central stylet, said stylet hub being configured to be releasably affixed to a needle hub.

**21.** The apparatus of claim **20** wherein the stylet hub comprises a control mechanism to facilitate advancement of the stylet beyond a distal end of the inner tube in a momentary fashion.

**22.** The apparatus of claim **1** further comprising an electrical pathway between an external electrical power source and a distal tip of the apparatus.

**23.** The apparatus of claim **22** wherein the electrical power source operates in the radiofrequency range.

**24.** The apparatus of claim **22** wherein the electrical power source provides sufficient current as to cut through tissue.

**25.** The apparatus of claim **22** wherein the electrical power source provides sufficient current as to cauterize tissue.

57

26. The apparatus of claim 1 further comprising a cutting stylet configured to cut a wider incision than an outside diameter of the outer tube.

27. A method of accessing a body cavity or lumen comprising the steps of:

Introducing a catheter into a mammalian body from a superior approach through an access channel;

Wherein the catheter comprises at least one side window; Advancing a steerable endoluminal punch such that a bendable region is aligned with the side window in the catheter;

Bending the bendable region of the steerable endoluminal punch such that a tip of the steerable endoluminal punch is forced radially outward away from an axis of the catheter;

Producing axial force on the endoluminal punch;

Generating off-axis forces at the tip of the steerable endoluminal punch by forcing the catheter into a wall of the access channel;

58

Puncturing a target region in the mammalian body with the steerable endoluminal punch distal end;

Inserting a guidewire through a center channel of the steerable endoluminal punch; and

5 Removing the steerable endoluminal punch leaving the guidewire in place.

28. The method of claim 27 further comprising the step of inserting a dilator into a central lumen of the catheter prior to advancing the steerable endoluminal punch into the catheter.

15 29. The method of claim 27 further comprising the step of inserting a dilator into a central lumen of the catheter wherein the dilator comprises a side window that can be aligned with the side window of the catheter.

30. The method of claim 27 further comprising the step of bending the steerable endoluminal punch to approximately 90 degrees or greater from the axis of the catheter.

\* \* \* \* \*